

ALLEGHENY MILLWORK

EMERGENCY ACTION PLAN

Interior Finish Trades – Divisions 06, 08 & 10
Commercial Construction

Compliant with:
Federal OSHA: 29 CFR 1926 (Construction)
Federal OSHA: 29 CFR 1910 (Referenced General Industry Standards)
NFPA 241: Safeguarding Construction, Alteration & Demolition Operations

Project Name	
Project Address	
General Contractor	
Effective Date	
Revision No.	

EMERGENCY ACTION PLAN

TABLE OF CONTENTS

Purpose & Scope..... 4

 Purpose..... 4

 Scope of Work Covered..... 4

 Applicability..... 4

Regulatory Authority & Compliance References 5

 Federal OSHA Standards (29 CFR 1926)..... 5

 OSHA General Industry Standards Referenced 6

 Other Applicable Codes & Standards 6

Definitions 7

Roles & Responsibilities..... 8

 Company Officer/Owner..... 8

 Safety Director 8

 General Superintendent..... 8

 Superintendent 8

 Designated First-Aid/AED Responders 8

 All Employees 8

Emergency Reporting & Communication 9

 Alarm Signals 9

 Backup Communication 9

 Reporting an Emergency: Sequence..... 9

 Information to Provide to 911 9

 Communication Equipment 10

Evacuation Procedures..... 11

 General Evacuation Rules 11

 Primary & Secondary Routes..... 11

 Trade Specific Evacuation Considerations..... 11

 Muster Point & Accountability 12

 Persons with Disabilities or Limited Mobility 12

Critical Operations Before Evacuation 13

Specific Emergency Procedures 14

 Fire & Smoke 14

 Medical Emergency/Serious Injury 14

 Severe Weather 14

 Electrical Emergency/Electrocution 15

 Falls from Heights 15

Hazardous Substance Release/Spill	16
Structural Collapse/Trench/Confined Space	16
Workplace Violence/Active Shooter	16
Bomb Threat/Suspicious Package.....	17
Civil Disturbance/Site Lockdown	17
Pandemic/Communicable Disease.....	17
Training & Drills	18
Initial Training.....	18
Refresher Training	18
Drills	18
Documentation.....	18
Medical Services & First Aid.....	19
First Aid Provider	19
First Aid Supplies	19
Bloodborne Pathogens.....	19
Eye Wash & Emergency Shower	19
Coordination with the General Contractor & AHJ	20
Plan Maintenance & Recordkeeping	21
Plan Review	21
Recordkeeping	21
Emergency Contact List	Appendix A
Site-Specific Emergency Action Plan	Appendix B
Evacuation Drill Report Form	Appendix C
Bomb Threat Checklist.....	Appendix D
Employee Training Acknowledgement	Appendix E
Incident/Near Miss Initial Report	Appendix F

PURPOSE & SCOPE

PURPOSE

Allegheny Millwork's Emergency Action Plan (EAP) establishes the procedures, responsibilities, and resources required to protect employees, subcontractors, visitors, and the public from injury and property loss during emergencies on commercial construction projects performed by this company. It is written to satisfy the Occupational Safety and Health Administration (OSHA) requirements of 29 CFR 1926.35 (Employee Emergency Action Plans, Construction) and the corresponding general industry standard 29 CFR 1910.38 and is intended to integrate with the General Contractor's (GC) site-specific safety program.

SCOPE OF WORK COVERED

This EAP applies to all field operations performed by Allegheny Millwork under the following Construction Specifications Institute (CSI) MasterFormat divisions:

- Division 06: Rough Carpentry, Finish Carpentry, and Architectural Millwork (blocking, wall and ceiling framing, sheathing, plywood and panel installation, casework, paneling, running and standing trim, stair parts, and shop-fabricated millwork).
- Division 08: Doors, Frames, Hardware, and Glazing (hollow metal frames and doors, wood doors, aluminum entrances and storefronts, finish hardware, automatic operators, interior glazing, mirrors, fire-rated assemblies, and curtain wall components installed from the interior).
- Division 10: Specialties (visual display units, signage, toilet compartments and accessories, lockers, fire extinguishers and cabinets, operable partitions, wall and corner guards, and similar finish specialty items).

APPLICABILITY

This plan applies to every Allegheny Millwork employee and to any subcontractor, vendor representative, delivery driver, or visitor under Allegheny Millwork's direction while on a project site. Where the General Contractor, Owner, or Authority Having Jurisdiction (AHJ) has issued a more stringent project-specific or building-specific emergency plan, the more protective requirement governs. This EAP is reviewed and amended at the start of every project to reflect site-specific conditions.

REGULATORY BASIS & COMPLIANCE REFERENCES

Allegheny Millwork's Plan has been prepared to satisfy the following regulatory requirements. Allegheny Millwork shall remain current with all amendments and shall update the Plan accordingly.

OSHA CONSTRUCTION STANDARDS (29 CFR 1926)

Citation	Subject
29 CFR 1926.20	General Safety & Health Provisions
29 CFR 1926.21	Safety Training & Education
29 CFR 1926.21	Definitions (Including Competent Person)
29 CFR 1926.34	Means of Egress
26 CFR 1926.35	Employee Emergency Action Plans (EAP)
29 CFR 1926.50	Medical Services & First Aid
29 CFR 1926.51	Sanitation
29 CFR 1926.95 – 106	Personal Protective Equipment & Life Saving Equipment
29 CFR 1926.150	Fire Protection
29 CFR 1926.151	Fire Prevention
29 CFR 1926.152	Flammable Liquids
29 CFR 1926.154	Temporary Heating Devices
29 CFR 1926.350 – 354	Welding & Cutting
29 CFR 1926 Subpart P	Excavations**
29 CFR 1926 Subpart AA	Confined Spaces in Construction
29 CR Subpart CC	Cranes & Derricks**

***Not typical to Allegheny Millwork's Scope of Work.*

OSHA GENERAL INDUSTRY STANDARDS REFERENCED

Citation	Subject
29 CFR 1910.36	Design & Construction of Exit Routes
29 CFR 1910.37	Maintenance, Safeguards & Operational Features for Exit Routes
29 CFR 1910.38	Emergency Action Plans
29 CFR 1910.39	Fire Prevention Plans
29 CFR 1910.157	Portable Fire Extinguishers
29 CFR 1910.165	Employee Alarm Systems
29 CFR 1910.1200	Hazard Communications
29 CFR 1910.1030	Bloodborne Pathogens
29 CFR 1904	Recording & Reporting Occupational Injuries & Illnesses

OTHER APPLICABLE CODES & STANDARDS

- **International Building Code (IBC)**: current adopted edition, as adopted by the AHJ
- **International Fire Code (IFC)**: current adopted edition, including Chapter 33 (Fire Safety During Construction and Demolition)
- **NFPA 241**: Standard for Safeguarding Construction, Alteration, and Demolition Operations
- **NFPA 101**: Life Safety Code
- **NFPA 51B**: Standard for Fire Prevention During Welding, Cutting, and Other Hot Work
- **NFPA 70/70E**: National Electrical Code and Standard for Electrical Safety in the Workplace
- **ANSI Z358.1**: Emergency Eyewash and Shower Equipment
- Local building, fire, and AHJ requirements
- Applicable State Plan OSHA requirements (where the project is in a State Plan jurisdiction)
- EPA, DOT, and state environmental requirements for hazardous materials, where applicable

DEFINITIONS

Term	Definition
AHJ	Authority Having Jurisdiction: the organization, office or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, an installation or a procedure.
Assembly Point/Muster Point	A predetermined safe location away from the structure where evacuated personnel gather for accountability.
Competent Person	An individual who is capable of identifying existing and predictable hazards in the surroundings or working conditions which are unsanitary, hazardous or dangerous to employees, and who has the authorization to take prompt corrective measures to eliminate them (29 CFR 1926.21(f)).
Designated Rescuer	A trained, equipped and preidentified employee authorized to perform limited rescue (i.e. first aid, AED use). Allegheny Millwork does not perform technical rescue (confined space, high-angle, structural collapse); those are summoned from the local fire/EMS service.
EAP	Emergency Action Plan: Written Plan required by 29 CFR 1926.35 and 29 CFR 1910.38.
EAP Coordinator	The person designated by Allegheny Millwork to maintain, train on and execute this plan at the project level (typically Superintendent/Competent Person)
Egress	A continuous and unobstructed path of vertical and horizontal travel from any point in a building or structure to a public way.
Hot Work	Any work involving open flames, sparks or heat, including welding, cutting, brazing, soldering, grinding and the use of torches.
Imminent Danger	Any condition or practice that could reasonably be expected to cause death or serious physical harm before such condition or practice can be abated through normal procedures.
Multi-Employer Worksite	A worksite where employees of more than one employer are present, as addressed by OSHA's Multi-Employer Citation Policy (CPL 02-00-124).
SDS	Safety Data Sheet; Formally known as MSDS.
Shelter-in-Place	Procedure to remain inside the structure or in a designated safe area when evacuation would create greater hazard.
State Plan	A state operated occupational safety & health program approved by Federal OSHA under Section 18 of the OSHA Act.

ROLES & RESPONSIBILITIES

COMPANY OFFICER/OWNER

- Approves and funds this EAP and the resources needed to implement it.
- Reviews and signs the plan annually and after every reportable incident.

SAFETY DIRECTOR

- Maintains the master EAP template, training records, and incident logs.
- Conducts annual program audits and reviews state-specific addenda.
- Coordinates with OSHA, insurance carriers, and legal counsel after a recordable event.

GENERAL SUPERINTENDENT (EAP COORDINATOR)

- Completes the Site-Specific EAP Addendum (Appendix A) before mobilization.
- Confirms muster points, evacuation routes, alarm signals, and EMS response with the GC.
- Holds the new-hire EAP orientation and the weekly toolbox talks.
- Initiates emergency response, calls 911, performs head-count at muster, and reports to the GC.
- Maintains the project emergency contact roster and posts it at each work area.

SUPERINTENDENT

- Acts as Coordinator in the Superintendent's absence.
- Performs daily pre-task hazard analysis (Job Hazard Analysis / Job Safety Analysis).
- Accounts for every crew member at the muster point and reports status to the Superintendent.

DESIGNATED FIRST AID/AED RESPONDERS

- Maintain current First Aid, CPR, and AED certification (American Red Cross, American Heart Association, or equivalent).
- Render aid within the scope of their training only; do not move a seriously injured worker except to remove from imminent danger.
- Inventory and inspect the first-aid kit weekly per 29 CFR 1926.50 and ANSI/ISEA Z308.1.

ALL EMPLOYEES

- Know the location of exits, fire extinguishers, eye-wash stations, first-aid kits, and the muster point for the area in which they are working.
- Recognize the project's alarm signal(s) and respond immediately when activated.
- Report to the muster point upon evacuation; remain there until released by the Superintendent or GC.
- Report any near-miss, injury, fire, spill, or unsafe condition to the Superintendent/Competent Person without delay.

EMERGENCY REPORTING & COMMUNICATION

ALARM SIGNALS

Each Allegheny Millwork project will adopt the alarm signals established by the General Contractor. In the absence of an established signal, Allegheny Millwork will use the methods below. The signal in use must be entered on the Site-Specific Addendum and communicated at orientation.

Signal	Meaning	Action
Continuous Horn or Alarm Tone for ≥30 Seconds	FIRE/EVACUATE	Immediate Evacuation to Assembly Area
Three (3) Short Blasts, Repeated	MEDICAL EMERGENCY	Clear Path for Responders. Do Not Evacuate Unless Directed
One (1) Long Blast Followed by Verbal Announcement	SHELTER-IN-PLACE	Move to Designated Interior Safe Area
Verbal Command “ALL CLEAR” by Superintendent	RESUME WORK	Return to Work Area Only When Authorized

BACKUP COMMUNICATION

- All Superintendents/Competent Persons shall carry charged two-way radios on the project channel.
- A current emergency contact list (Appendix A) shall be posted at the trade trailer, Conex, or designated muster sign.
- Cellular phones are acceptable as a tertiary means; reliance on cellular alone is not permitted.

REPORTING AN EMERGENCY: SEQUENCE

1. Ensure your own safety first; do not enter a hazardous area to investigate.
2. Activate the nearest fire-alarm pull station, if present, for fire or smoke.
3. Call 911 from a cell phone or the nearest landline; remain on the line until released by the dispatcher.
4. Notify the Project Superintendent and the GC Superintendent by radio or phone.
5. Send a runner or post a flagger at the project entrance to direct EMS/Fire personnel to the incident location.
6. Begin evacuation or shelter procedure as appropriate.

INFORMATION TO PROVIDE TO 911

- Project name and physical address (use the address posted at the gate, not the legal description).
- Nearest cross street or building entrance.
- Nature of emergency (fire, fall, laceration, chemical exposure, unconscious worker, etc.).
- Number and condition of injured or trapped persons.

- Hazards on site (energized work, hot work, oxy-fuel cylinders, chemicals, height of fall, etc.).
- Your name and call-back number; remain on the line until released.

COMMUNICATION EQUIPMENT

- Each crew will be issued at least one (1) two-way radio set to the project channel.
- Each Superintendent/Competent Person carries a cell phone with the emergency roster preloaded.
- An air horn is staged at every crew gang box for use when radio or alarms are unavailable.
- The emergency roster (Appendix A) is posted at each gang box, the field office, and the muster point.

EVACUATION PROCEDURES

GENERAL EVACUATION RULES

- Stop work immediately; do not finish the cut, set, or pour.
- Deenergize portable tools; close gas cylinder valves where it can be done in seconds without delaying evacuation.
- Walk, do not run, to the nearest safe exit; do not use elevators or material hoists.
- Assist anyone with a mobility limitation; use a partner system for evacuation from upper floors.
- Close (but do not lock) doors behind you to limit the spread of fire/smoke.
- Proceed to the assigned muster point and remain there for headcount.
- Do not re-enter the building until the General Contractor or Fire Department issues the all-clear.

PRIMARY & SECONDARY ROUTES

At least two means of egress are maintained from every work area at all times, in accordance with 29 CFR 1926.34. Exit routes must remain unblocked by carts, lifts, scaffold, material, debris, glass crates, door stacks, or panel carts. Foremen verify exit-route clearance during the daily pre-shift walk.

TRADE SPECIFIC EVACUATION CONSIDERATIONS

Division 06: Carpentry & Millwork

- Power down table saws, miter saws, routers, and panel saws; leave material on the saw rather than carry it to evacuation.
- Set downloaded panel carts on a stable surface and chock the wheels before leaving.
- Pneumatic nailers and powder-actuated tools must be disconnected from the air or magazine source as the operator leaves the workstation if it can be done in three (3) seconds or less.
- Stacked millwork casework, paneling, and trim must not block the egress path; staged material is held back a minimum of 36 inches from any exit, stair, or rated corridor.

Division 08: Doors, Frames, Hardware & Glazing

- Set glass Lites or insulated glazing units (IGUs) into a glass rack, cart, or against the substrate before evacuating — never leave glass freestanding in an egress path.
- Frames stacked on dollies must be strapped and braced before workers leave the floor.
- Aluminum storefront and curtain wall components must be secured against wind uplift before evacuating during a severe-weather warning.
- Where new hardware has been installed but doors are not yet keyed, ensure the door does not lock evacuees behind it; wedge the door open or remove the latching strike during installation.
- Silicone, butyl, and solvent cleaners must be capped immediately during a fire alarm; do not leave saturated rags in the work area.

Division 10: Specialties

- Operable partitions in transit on a track must be parked and braked before evacuation.
- Toilet compartment stacks, locker shipments, and visual display units must be stored so they cannot topple into the exit path during a seismic, wind, or stampede event.
- Mounted but un-grouted fire extinguisher cabinets and corner guards must be secured against falling before leaving the area.

MUSTER POINT & ACCOUNTABILITY

- Each work floor has a primary and secondary muster point identified on the Site-Specific Addendum.
- On arrival, each employee reports by name to their Superintendent, who marks the daily roster.
- Superintendent report 'all accounted for' or '____ unaccounted for, last seen at ____' to the General Contractor Safety Manager within five (5) minutes of evacuation.
- The Superintendent provides the consolidated headcount to the General Contractor and Fire Department Incident Commander.
- Under no circumstance will Allegheny Millwork employees re-enter the building to search for a missing worker, that information is conveyed to the Fire Department, who will perform any rescue.

PERSONS WITH DISABILITIES OR LIMITED MOBILITY

- Any employee with a temporary or permanent limitation that may affect self-evacuation must notify the Superintendent at orientation. Allegheny Millwork will arrange a buddy system and pre-identify an Area of Refuge (typically the rated stair landing) for use until the Fire Department arrives.
- Information shared regarding a disability is treated as confidential medical information under the ADA and is shared only with personnel who need to know to perform an evacuation.

CRITICAL OPERATIONS BEFORE EVACUATION

In limited circumstances, certain operations must be shut down before evacuation to prevent escalation. Only trained employees specifically designated for these tasks remain behind, and they leave as soon as the shutdown is complete or whenever shutdown would delay their own escape.

Operation	Shutdown Step	Authorized Personnel
Hot Work (welding/cutting) on Metal Frames or Curtain Wall	1. Close fuel-gas & oxygen cylinder valves 2. Turn off Welder 3. Remove ignition sources	Hot Work Permit Holder Only
Compressed Air System Feeding Pneumatic Nailers	1. Close the Compressor Outlet Valve 2. Bleed the Line	Superintendent or Designee
Adhesive/Solvent Open Containers (millwork, glazing)	1. Recap Containers 2. Remove Saturated Rags to a Metal Lidded Waste Can	User of Workstation, Time Permitting Only
Powered Lifts (Scissor/Boom) at Height	1. Lower Platform to Ground & Disable 2. Do NOT Delay Personal Evacuation	Trainer Operator Only
Temporary Lighting/Power	1. Leave Energized for Egress – Do Not Deenergize	N/A

If shutdown cannot be completed safely within sixty (60) seconds, abandon the task and evacuate. No property, tool or material is worth someone's life. Objects can be replaced, your life cannot!

SPECIFIC EMERGENCY PROCEDURES

FIRE AND SMOKE

- Activate the nearest pull station and call 911.
- Use a portable extinguisher (PASS: Pull, Aim, Squeeze, Sweep) only if: the fire is incipient (smaller than a waste can); the employee has been trained per 29 CFR 1926.150 and 1910.157; the exit is at the user's back; and the air is breathable.
- Combustible loads on interior trades; sawdust, wood scrap, cardboard cartons from millwork and casework, foam blocking, solvent rags, polyurethane finishes, contact cement, and silicone, must be removed daily and at the end of every shift per 29 CFR 1926.252 and NFPA 241.
- Hot-work permits are required for all welding, cutting, brazing, soldering, and grinding within the project, and a dedicated fire watch is maintained during work and for a minimum of thirty (30) minutes after work is complete (longer if required by the General Contractor or NFPA 51B).
- Smoking is permitted only in designated, marked outdoor areas approved by the General Contractor.

MEDICAL EMERGENCY/SERIOUS INJURY

- Survey the scene for hazards before approaching (energized circuits, fall hazard, traffic, fire, structural compromise).
- Designated First Aid Responder renders aid within the scope of training; bystanders summon the Superintendent and 911.
- Apply universal precautions; gloves and barrier device, for any contact with blood or bodily fluids (29 CFR 1910.1030).
- Do not move a worker with a suspected spinal, head, or fracture injury unless leaving them in place would cause greater harm.
- Bring the AED to the scene for any unresponsive worker; use as trained.
- Do not remove an embedded object (e.g., a fastener, glass shard, or splinter penetrating the body), stabilize and wait for EMS.
- Send a runner to the site entrance to escort EMS to the patient.
- Notify the Safety Director and Human Resources within one (1) hour of any injury requiring transport for medical treatment.

SEVERE WEATHER

Tornado/High Wind Warning

- Cease exterior glazing, frame, and storefront work; secure or remove un-glazed Lites from openings; remove or weight loose materials.
- Move personnel to the designated shelter location; typically, the lowest interior corridor, stairwell, or core area away from glazed openings.
- Curtain wall and storefront crews stage all open material in a strapped cart against an interior wall before sheltering.

- Note: Allegheny Millwork does possess a Tornado Preparedness Plan & Checklist, which is available upon request.

Lightning

- Suspend exterior work and metal-frame/curtain wall work when lightning is within ten (10) miles per the 30/30 rule; do not resume until thirty (30) minutes after the last observed strike or thunder.
- Move scissor lifts and boom lifts away from steel structure to a non-elevated parked position.

Hurricane/Tropical Storm

- Initiate the General Contractor's hurricane plan at the Tropical Storm watch (typically 48 hours out); brace doors and partitions, strap glazing carts, remove or secure jobsite trailers, and tarp millwork.
- Demobilize crews at the time established by the General Contractor; do not return until the General Contractor reopens the site.
- Note: Allegheny Millwork does possess a Hurricane Preparedness Plan & Checklist, which is available upon request.

Heat & Cold

- Heat illness: increase water and electrolyte intake (one cup per 15 minutes), schedule rest in shade, acclimatize new and returning workers per the OSHA Heat Illness Prevention Campaign.
- Cold stress: provide warming areas, monitor for shivering and confusion, rotate workers per OSHA cold-stress guidance.
- Where applicable state heat-illness standards exist (e.g., California Title 8 §3395, Washington WAC 296-62-095, Oregon OAR 437-002-0156, Nevada NRS 618), those standards govern and the project takes the more protective measure.
- Note: Allegheny Millwork does possess both a Heat Illness Plan and a Cold Stress Plan, as well as state specific Heat Illness Plans, which are available upon request.

ELECTRICAL EMERGENCY/ELECTROCUTION

- Do not touch a worker in contact with an energized source.
- De-energize at the panel or call the GC to do so; if not possible, use a non-conductive object (dry wood, fiberglass) to separate the victim only if the circuit is known to be ≤ 480 V.
- Begin CPR / AED once the victim is clear of the source.
- Treat the worker for both electrical burns and likely cardiac involvement; transport in all cases of confirmed shock above the perception threshold.

FALLS FROM HEIGHT

- Carpentry blocking, ceiling-grid work, casework anchoring at height, door-closer installation, transom glazing, and high specialty mounting often expose crews to fall hazards above six (6) feet (29 CFR 1926 Subpart M).

- A worker suspended in a personal fall arrest system must be rescued within fifteen (15) minutes to prevent suspension trauma. Pre-plan rescue method (self-rescue trauma straps, MEWP retrieval, or fire-department rescue) before each elevated task.
- If a fall occurs, stabilize the victim in position, summon 911, and prepare for retrieval by trained rescuers; do not cut a suspension lanyard while the worker is suspended.
- Note: Allegheny Millwork does possess a Fall Prevention Program and Plan, available upon request.

HAZARDOUS SUBSTANCE RELEASE/SPILL

- Common products on these trades; contact cement, solvent-based wood finishes, polyurethane, silicone and butyl sealants, MDF dust, isocyanate-containing adhesives, lead-paint dust on demo, and glass-cleaning solvents, are managed under Allegheny Millwork's Hazard Communication Program (29 CFR 1926.59/1910.1200).
- On a release, evacuate the immediate area, ventilate if possible, and consult the Safety Data Sheet (SDS) before cleanup. SDSs are maintained at the field office and digitally on each Superintendent/Competent Person's device.
- For a release that cannot be contained with the spill kit on hand, call 911 and the National Response Center at 1-800-424-8802 if any quantity reaches a drain, soil, or surface water.
- Asbestos or lead encountered unexpectedly during demolition or selective demolition of existing partitions, doors, or finishes: stop work, secure the area, notify the GC immediately, and do not resume until tested and abated by a licensed contractor (29 CFR 1926.1101 / 1926.62).
- Respirable crystalline silica during cutting, drilling, or grinding of masonry, tile substrate, or fiber-cement components: follow Table 1 controls of 29 CFR 1926.1153.
- Note: Allegheny Millwork does possess a Respirable Crystalline Silica Program and a Silica Emergency Control Plan, which are available upon request.

STRUCTURAL COLLAPSE/TRENCH/CONFINED SPACE

- Although these trades rarely create excavations or confined spaces, employees may work near them. In the event of a collapse: do not enter the affected area, call 911, and report to the General Contractor. Allegheny Millwork does not perform technical rescue.
- Some millwork installations (e.g., in IT closets, mechanical rooms, or built-in cabinetry inside tanks) qualify as Permit-Required Confined Spaces under 29 CFR 1926 Subpart AA. A separate entry permit and rescue plan is required before entry.

WORKPLACE VIOLENCE/ACTIVE SHOOTER

- **RUN:** leave the area if a safe path exists, leaving belongings behind.
- **HIDE:** if you cannot run, lock or barricade yourself in a room out of the assailant's view; silence phones; spread out.
- **FIGHT:** only as a last resort and only if your life is in imminent danger; act with aggression and improvise weapons.
- When law enforcement arrives: keep hands visible and empty; follow instructions exactly; do not approach officers.

- Report all threats, harassment, intimidation, or weapons sightings to the Superintendent and General Contractor immediately.

BOMB THREAT/SUSPICIOUS PACKAGE

- Take the threat seriously; if received by phone, keep the caller talking, signal a co-worker to call 911, and record exact wording, voice characteristics, and background sounds (DHS bomb threat checklist).
- Do not touch, move, or transmit on a two-way radio or cell phone within 50 feet of a suspicious package.
- Evacuate per the Evacuation Procedures Section; allow law enforcement to clear the site before reentry.

CIVIL DISTURBANCE/SITE LOCKDOWN

- Follow the direction of the General Contractor and law enforcement; do not leave the site if a lockdown is in effect.
- Move away from windows, glazed entrances, and storefront openings to an interior area.

PANDEMIC/COMMUNICABLE DISEASE

- Follow the General Contractor's site infection-control plan, applicable CDC guidance, and any state or local public-health orders in effect at the time of the project.
- Workers who exhibit symptoms of a communicable disease should not report to work; report to the Superintendent/Competent Person by phone.

TRAINING & DRILLS

INITIAL TRAINING

Each employee receives EAP training before being assigned to a project, with the following content (29 CFR 1926.35(e)):

- The contents and location of this written plan.
- The recognized alarm signals and reporting procedure for this project.
- Primary and secondary evacuation routes and muster points for the work area assigned.
- Shutdown procedures, if any, the employee is responsible for.
- How to summon medical assistance and report a fire.
- Trade-specific hazards and emergency considerations.
- Identity of the EAP Coordinator and the Designated First Aid Responders for the project.

REFRESHER TRAINING

- Whenever an employee's responsibilities under the plan change.
- Whenever the plan itself is changed.
- When initial training shows that an employee does not have an adequate understanding.
- At minimum annually as a documented refresher.

DRILL FREQUENCY

- An evacuation drill shall be conducted at least annually for the trade crew, or more frequently if required by the General Contractor, AHJ, or project conditions.
- On long-duration projects (greater than 12 months), drills shall occur at least every six (6) months.
- Drills shall include at least one (1) unannounced drill.
- On occupied-building renovation projects, drill schedules shall be coordinated with the building owner and the General Contractor.

DRILL EVALUATION

Each drill shall be observed and documented. The drill report shall record:

- Date, time, type (announced/unannounced), and scenario.
- Time elapsed from alarm to last person at assembly area.
- Number of personnel evacuated and accounted for.
- Issues identified — alarm audibility, blocked egress, missing wardens, confused workers, equipment problems.
- Corrective actions and target completion dates.
- Signature of the Emergency Coordinator and General Contractor representative.

A sample drill report form is provided in Appendix C.

DOCUMENTATION

Training rosters, refresher logs, drill records, and corrective actions are retained for the duration of the project plus three (3) years (or longer where state law or contract requires).

MEDICAL SERVICES & FIRST AID

FIRST AID RESPONDER

- In accordance with 29 CFR 1926.50(c), in the absence of an infirmary, clinic, hospital, or physician reasonably accessible in terms of time and distance, at least one employee on each crew shall have a valid certificate in first-aid training from the U.S. Bureau of Mines, the American Red Cross, the American Heart Association, or equivalent.
- The nearest 24-hour emergency medical facility and route are identified in Appendix B and posted at the field office.

FIRST AID SUPPLIES

- First aid kits meeting ANSI/ISEA Z308.1 Class B or higher are maintained on each project, inspected weekly, and re-stocked after every use.
- AEDs are recommended on all projects; where provided, they are inspected monthly per manufacturer and AHA guidelines.

BLOODBORNE PATHOGENS

First Aid Responders are covered under Allegheny Millwork's Exposure Control Plan (29 CFR 1910.1030). Universal precautions, gloves, and barrier devices are provided in every kit; sharps and contaminated waste are disposed of per the plan.

EYE WASH & EMERGENCY SHOWER

- Where workers handle injurious corrosive materials (e.g., certain solvent cleaners or epoxy hardeners used in glazing and millwork), suitable facilities for quick drenching or flushing of the eyes and body are provided within the work area for immediate emergency use (29 CFR 1926.50(g) and ANSI Z358.1).
- At minimum, portable 16-oz emergency eyewash bottles are staged in the gang box; a plumbed or self-contained 15-minute unit is installed where required by the SDS.

COORDINATION WITH THE GENERAL CONTRACTOR & AHJ

- At premobilization, the Superintendent obtains the General Contractor's site-specific safety plan, EAP, alarm signals, muster points, lockout authorities, hot-work permitting procedure, and emergency contact list.
- The Site-Specific Addendum (Appendix B) is signed by Allegheny Millwork's Superintendent and acknowledged by the General Contractor.
- Where this EAP and the General Contractor's plan differ, the more protective requirement governs.
- On occupied building projects (interior fit-out, tenant improvement), Allegheny Millwork coordinates with the building owner and the local Fire Marshal regarding alarm test schedules, fire-watch requirements during impaired sprinkler or alarm conditions, and access through occupied corridors.
- OSHA reporting: any work-related fatality is reported within eight (8) hours, and any in-patient hospitalization, amputation, or loss of an eye is reported within twenty-four (24) hours, to the OSHA Area Office or 1-800-321-OSHA (6742) (29 CFR 1904.39).

PLAN MAINTENANCE & RECORDKEEPING

PLAN REVIEW

- This Plan shall be reviewed at minimum annually by Allegheny Millwork's Safety Director and the Superintendent/Competent Person.
- The Plan shall also be reviewed and updated upon any change in scope, site, hazards, regulations, or after any actual emergency or drill that identifies a deficiency.
- Reviews shall be documented and signed.
- The Site-Specific Addendum is created at every project mobilization and revised whenever site conditions change.
- A current copy of this EAP is available for review by any employee at the field office (29 CFR 1926.35(d); required to be made available to employees for the small-employer threshold; provided in writing as best practice regardless of employer size).

RECORDKEEPING

Record	Retention Period
Emergency Action Plan & Revisions	Duration of Project + Three (3) Years
Training Records	Employment + Three (3) Years (Or longer per State Requirements)
Drill Reports	Five (5) Years
Hot Work Permits	One (1) Year Minimum, Longer if Required by AHJ
Inspection Records (Extinguishers, Egress, Lighting)	One (1) Year Minimum
OSHA Form 300, 300A, 301	Five (5) Years, per 29 CFR 1904.33
Medical & Exposure Records	Per 29 CFR 1910.1020 (Typically 30 Years)