

ALLEGHENY MILLWORK

HEAT ILLNESS PREVENTION PLAN

Interior Finish Trades – Divisions 06, 08 & 10
Commercial Construction – State of Nevada

*Compliant with Nevada OSHA – Division of Industrial Relations
Nevada Administrative Code (NAC) Chapter 608: Regulation R131-24AP
Heat Illness Prevention (Effective April 29th, 2025)*

Project Name	
General Contractor	
Effective Date	

HEAT ILLNESS PREVENTION PLAN

TABLE OF CONTENTS

Purpose & Scope.....	4
Nevada Regulatory Framework (Nevada OSH/NAC 618)	5
Applicability.....	5
Core Requirements of R131-24AP.....	5
Key Distinction from Other State Plans	6
Heat Illness National Emphasis Program & Heat Priority Days	6
Other Applicable Requirements	6
Job Hazard Analysis (JHA) Requirement.....	7
Allegheny Millwork JHA Findings: Division 06, 08 & 10	7
Mitigation Hierarchy	7
Jobsite & Emergency Contacts	8
Responsibilities	10
Employer/Management	10
Superintendents/Competent Person(s)	10
Employees, Subcontractors & Installers	11
Heat Related Illnesses: Signs, Symptoms & Treatment	12
Heat Stroke	12
Heat Exhaustion.....	13
Heat Cramps	13
Heat Syncope	14
Heat Rash	14
Interior Heat & Humidity Hazard Identification.....	15
Division 06 – Rough & Finish Carpentry/Architectural Millwork.....	15
Division 08 – Doors, Frames, Hardware & Glazing	15
Division 10 – Specialties	15
Monitoring of Working Conditions.....	17
What to Monitor	17
How to Monitor	17
Remote/Solo Worker Monitoring.....	17
Potable Water & Hydration Requirements	19
Water Provision	19
Hydration Guidance for Employees	19
Rest Breaks & Cool Down Periods	20
Rest Break Schedule (Heat-Index Based: Best Practice).....	20
Rest Break Requirements.....	20

Means of Cooling: Interior Work.....	21
Preferred Cooling Methods (Hierarchy).....	21
Cooling Area Requirements.....	21
Coordination with the General Contractor	22
Acclimatization Schedule	23
Acclimatization Schedule	23
Acclimatization Policies	23
Heat Priority Day Procedures (90°F+).....	25
Heat Priority Day Activation	25
Heat Priority Day Requirements.....	25
Outdoor & Delivery Exposure Procedures	26
Outdoor Exposure Assessment	26
Delivery & Offloading Procedures	26
Outdoor Heat Index Thresholds & Actions	27
Work Clothing & Personal Protective Equipment (PPE)	28
Clothing Guidance.....	28
PPE Considerations for Heat.....	28
Emergency Response Procedures	29
Pre-Shift Emergency Preparedness.....	29
Emergency Response Steps	30
Recordkeeping After Incident	31
Training	32
Training Requirements by Role.....	32
Employees, Subcontractors & Installers.....	32
Superintendents/Competent Persons	32
Training Delivery	33
Program Review & Record Keeping	34
Plan Review Schedule	34
Records to be Maintained (5-Year Retention)	34
Heat Index Reference Chart	Appendix A
Interior Heat Source Checklist	Appendix B
Job Hazard Analysis Worksheet (R131-24AP)	Appendix C
Employee Acknowledgement Form.....	Appendix D

PURPOSE & SCOPE

Allegheny Millwork is committed to protecting every employee, subcontractor and installers from the hazards of heat illness. This Heat Illness Prevention Plan (HIPP) has been developed specifically for interior finish trades operating on commercial construction sites within the State of Nevada:

- Division 06: Rough & Finish Carpentry/Architectural Millwork
- Division 08: Doors, Frames, Hardware & Glazing
- Division 10: Specialties

Interior finish work presents unique heat hazards that differ significantly from outdoor construction. Enclosed spaces, reduced air exchange, proximity to mechanical and electrical equipment, elevated humidity from concrete curing, and limited access to natural breezes can produce dangerously high ambient temperatures and heat indices independent of the outdoor temperature. Nevada's desert climate compounds these risks: outdoor temperatures in Las Vegas, Henderson, Reno, and other Nevada metropolitan areas routinely exceed 100°F during the heat season (May through September), and interior temperatures in unconditioned construction spaces frequently exceed outdoor temperatures due to thermal mass and lack of ventilation. This plan addresses interior-specific risks while also providing procedures for the outdoor exposure that occur during material deliveries and site access.

This plan is designed to comply with the Nevada Occupational Safety and Health Administration (Nevada OSHA), Division of Industrial Relations, under Nevada Administrative Code (NAC) Chapter 618 and Regulation R131-24AP: Heat Illness Prevention (effective April 29, 2025), as well as Nevada Revised Statutes (NRS) 618.375 (General Duty), NRS 618.383 (Written Safety Program), the federal OSHA General Duty Clause 29 U.S.C. § 654(a)(1), and NIOSH heat-stress guidance (Publication 2016-106).

NEVADA REGULATORY FRAMEWORK (NEVADA OSHA/NAC 618)

Nevada operates under its own OSHA-approved State Plan through Nevada OSHA, which is administered by the Nevada Division of Industrial Relations (DIR), Department of Business and Industry. Nevada OSHA's Heat Illness Prevention regulation, R131-24AP, was approved by the Legislative Commission on November 15, 2024 and became enforceable on April 29, 2025. Unlike some other state plans, Nevada's regulation is a performance-based standard that does not impose fixed numeric temperature triggers; instead, it requires employers to assess and mitigate occupational heat illness exposure through a written Job Hazard Analysis (JHA) and a written Heat Illness Prevention Plan.

APPLICABILITY

- Applies to all Nevada employers with more than ten (10) employees who are required to maintain a written safety program under NRS 618.383 (and to all employers engaged in the manufacturing of explosives, regardless of size).
- Applies to private employers and to State and Local Government employers. Does not apply to Federal employers.
- Applies to both indoor and outdoor workers. Indoor workers in climate-controlled environments (where temperature and humidity are actively regulated) are exempt from Sections 5-8 of R131-24AP, BUT if the climate-control system fails or fails to effectively address heat illness, the employer must restore it as soon as practicable and implement interim measures.
- All Nevada employers, regardless of size, remain obligated under NRS 618.375 to protect employees from recognized hazards, including heat illness.

CORE REQUIREMENTS OF R131-24AP

- Job Hazard Analysis (JHA): A one-time written JHA identifying job classifications in which the majority of employees have occupational exposure to heat illness for more than thirty (30) minutes of any sixty (60) minute period (excluding breaks). The JHA should be reviewed/revised when a task materially changes or following an accident (NAC 618.540).
- Superintendent/Competent Person: An employee with explicit authority to monitor working conditions, respond to heat illness emergencies, carry out the written safety program and appoint a designee (if needed).
- Written Heat Illness Prevention Plan: Included as a distinctly titled chapter within the NRS 618.383 written safety program covering:
 - Provision of potable water (per 29 CFR 1926.51 & 1910.141)
 - Rest breaks for any employee exhibiting signs/symptoms of heat illness
 - Means of cooling
 - Monitoring of working conditions
 - Identification and mitigation of work processes generating heat or humidity
 - Training
 - Procedures for medical emergency response
- Training: All employees in identified job classifications, plus the Superintendent/Competent Person must be trained before performing work duties.

- Emergency Medical Response: Procedures to contact EMS, provide reach-information and ensure transport when needed. The employer's responsibility ends when EMS makes physical contact with the employee.

KEY DISTINCTION FROM OTHER STATE PLANS

Nevada's regulation does not specify numeric temperature triggers (such as 80°F or 87°F). Compliance is measured by whether the employer's JHA accurately identifies heat-illness exposure and whether the written plan and field practices reasonably mitigate that exposure. This HIPP voluntarily incorporates conservative numeric triggers; drawn from ACGIH Threshold Limit Values, NIOSH criteria, the ANSI/ASSP A10.50-2024 Standard for Heat Stress Management in Construction, and OSHA Heat Index guidance, to ensure consistent field application and to exceed the regulatory floor.

HEAT ILLNESS NATIONAL EMPHASIS PROGRAM & HEAT PRIORITY DAYS

Pursuant to Nevada OSHA's May 4, 2022 guidance under the Heat Illness National Emphasis Program (NEP), any day on which the temperature reaches or exceeds 90°F is treated as a Heat Priority Day. On Heat Priority Days, Nevada OSHA may inspect any heat-related complaint, referral, or fatality regardless of industry, and on days under a National Weather Service heat warning or advisory, programmed inspections may be conducted in targeted high-risk industries (which include construction). This HIPP's Heat Priority Day Procedures (page 25) implement specific protective measures whenever this 90°F threshold is forecasted or reached at a Nevada project site.

OTHER APPLICABLE REQUIREMENTS

- OSHA General Duty Clause (Section 5(a)(1), 29 U.S.C. § 654(a)(1)): Workplaces must be free from recognized hazards likely to cause death or serious physical harm; including heat-related illness.
- NIOSH Criteria Document: Occupational Exposure to Heat & Hot Environments (Publication 2016-106); technical guidance referenced by Nevada OSHA inspectors.
- ACGIH Threshold Limit Values (TLVs) and Biological Exposure Indices, 2020 edition or later; adopted by reference in NAC Chapter 618 for Wet-Bulb Globe Temperature (WBGT) determinations.
- ANSI/ASSP A10.50-2024: Standard for Heat Stress Management in Construction.

JOB HAZARD ANALYSIS (JHA) REQUIREMENT

R131-24AP, Section 5, requires a one-time written Job Hazard Analysis for any job classification in which the majority of employees have occupational exposure to heat illness for more than thirty (30) minutes of any sixty (60) minute period (excluding breaks). The JHA must be reviewed, and if necessary, revised when a task materially changes (i.e. a change in environment, process or exertion level) and following any accident, in accordance with NAC 618.540.

ALLEGHENY MILLWORK JHA FINDINGS: DIVISIONS 06, 08 & 10

Allegheny Millwork has determined that the following job classifications, when performing work on Nevada commercial construction sites, routinely have occupational heat-illness exposure exceeding thirty (3) minutes of any sixty (60) minute period, and are therefore subject to the full requirements of R131-24AP:

- Finish Carpentry/Millwork Installation (Division 06)
- Door, Frame & Hardware Installation (Division 08)
- Glazier/Glazing Installation (Division 08)
- Specialties Installation: Toilet Partitions, Lockers, Bath & Shower Accessories Signage, FE Cabinets (Division 10)
- Field Superintendent/Lead Working Alongside Above
- Material Handler/Driver Assigned to Deliveries and Offloading

MITIGATION HIERARCHY

Per OSHA Publication 3071 and Nevada OSHA's January 29, 2025 guidance, hazard control measures are implemented in the following order of precedence:

- Engineering Controls (preferred): air conditioning, increased ventilation, cooling fans, reflective shielding from radiant heat, insulation of hot surfaces, sealing of steam leaks, shaded staging.
- Administrative & Work Practice Controls: scheduling hot tasks for cooler portions of the day; cool drinking water onsite within easy reach; work/rest schedules; rotation of personnel; reduction of physical demand.
- Personal Protective Equipment: hats and sun-protective clothing for outdoor work; loose, reflective, or cooling garments indoors; cooling vests where appropriate.
- Acclimatization & Health-Risk Awareness: 7-to-14-day acclimatization for new employees; advisement of medications and conditions that increase heat-illness risk.

A complete blank Job Hazard Analysis Worksheet is provided in Appendix C. The Superintendent shall complete or verify a project-specific JHA before any Allegheny Millwork crew begins work on a Nevada site.

JOBSITE EMERGENCY CONTACTS

The following contacts must be completed prior to the start of work and posted at the jobsite in a visible location. All employees must be made aware of these contacts during site orientation.

Role	Name	Phone Number
Project Manager		
Project Executive		
General Superintendent		
Superintendent		
Human Resources		
General Contractor Safety Rep		
Nearest Emergency Room		
Nearest Urgent Care		
Emergency Services		
Poison Control Center		
Nevada OSHA: Las Vegas Office		
Nevada OSHA: Reno Office		
Nevada SCATS (Free Consult)		

Allegheny Millwork is committed to ensuring that all its employees, subcontractors and installers are tended to as soon as possible when experiencing a heat-related illness. Below are the nearest hospital and urgent care facility, with driving directions, for employees, subcontractors or installers that need to be transported for any illness or injury while on the jobsite.

NEAREST HOSPITAL: ADDRESS & DRIVING DIRECTIONS

NEAREST URGENT CARE FACILITY: ADDRESS & DRIVING DIRECTIONS

RESPONSIBILITIES

The following outlines what critical role each member of the project and Allegheny Millwork team play when it comes to the execution of this Heat Illness Prevention Plan.

EMPLOYER/MANAGEMENT

Allegheny Millwork and its Management Team are responsible for:

- Developing, implementing and annually reviewing this Heat Illness Prevention Plan in compliance with NAC Chapter 618/R131-24AP, NRS 618.375 and NRS 618.383.
- Conducting and maintaining a one-time written Job Hazard Analysis for affected job classifications and reviewing/revising it when tasks materially change or after an accident (NAC 618.540).
- Designating a qualified, authorized person (General Superintendent & Superintendent) at each jobsite to perform the monitoring and emergency response functions required by R131-24AP, Section 6(2) and to appoint a designee.
- Ensuring every General Superintendent and Superintendent/Competent Person has received Nevada OSHA-compliant heat illness prevention training and is capable of identifying and responding to heat-related illnesses.
- Providing, at no cost to employees, adequate potable water [meeting 29 CFR 1926.51(a)(1) and 29 CFR 1910.141(a)(2)], means of cooling, rest opportunities and all required PPE related to heat-illness prevention.
- Ensuring that emergency response procedures are established, communicated and rehearsed before work begins.
- Maintaining all training records, acknowledgements, JHA documentation, monitoring logs and incident reports for the period required (More information on record retention can be found in the Recordkeeping Section of this Plan).
- Conducting post-incident reviews following any heat-related illness event and updating this plan accordingly (NAC 618.540).
- Ensuring this HIPP is written in English and Spanish (and additional languages as needed to reflect the primary language(s) of the workforce). A copy must be maintained at the jobsite and be available to employees and Nevada OSHA representatives upon request.

SUPERINTENDENTS/COMPETENT PERSON

The onsite Superintendent serves as the Designated Person/Competent Person under Section 6(1)(a) of R131-24AP and is responsible for:

- Carrying out the provisions of this HIPP and the broader written safety program required by NRS 618.383.
- Monitoring working conditions that could create occupational exposure to heat illness; including ambient temperature, relative humidity, radiant heat sources, air movement, workload and PPE burden; to the extent practicable.

- Recording temperature and humidity readings at the start of each shift and at midday in each primary work zone using a calibrated digital thermometer/hygrometer (or combined instrument) on Heat Priority Days (90°F+) and any day the JHA identified hazards are present.
- Identifying and documenting interior heat sources, including HVAC commissioning status, concrete cutting stages, proximity to boilers/heaters/mechanical rooms and glass envelope exposure on curtain wall scopes.
- Conducting pre-shift safety meetings daily covering heat illness signs and symptoms, hydration reminders, location of water and cooling areas and emergency procedures.
- If an employee is displaying signs of a possible heat illness, monitoring the employee to determine whether medical attention is necessary.
- If an employee is experiencing signs/symptoms requiring an emergency response:
 - Contacting EMS (or ensuring EMS is contacted)
 - Providing all information necessary for EMS to reach employee (Contact & Directions)
 - Ensuring the employee is, if necessary, transported to a location accessible to EMS
- Closely observing newly assigned employees during their acclimatization period (7-14 days) and observing all employees during heat waves.
- Appointing a qualified designee with the same authority as the Superintendent/Competent Person, available as backup when necessary.
- Coordinating with the General Contractor regarding HVAC commission, building envelope completion and any conditions affecting interior temperatures and humidity levels.
- Implementing feasible engineering and administrative controls to reduce heat exposure when conditions warrant.
- Carrying a charged, fully functional cell phone or two-way radio at all times during the shift to ensure effective communication for emergency response.

EMPLOYEES, SUBCONTRACTORS & INSTALLERS

Allegheny Millwork employees, subcontractors, and installers are responsible for:

- Knowing, understanding, and following this Heat Illness Prevention Plan at all times.
- Recognizing the signs and symptoms of heat-related illness in themselves and in coworkers.
- Maintaining adequate hydration throughout the shift by drinking water frequently, not waiting until thirsty.
- Taking rest breaks as needed and as directed in designated cool/shaded areas. Any employee who feels heat-related symptoms or believes they need to recover from heat must be permitted a rest period of not less than five (5) minutes (R131-24AP Section 9/NAC 618 Sec. 9.2).
- Following the Buddy System: actively observing coworkers for signs and symptoms of heat illness and reporting concerns to the Superintendent/Competent Person immediately.
- Immediately reporting any heat-related illness symptoms; your own or a coworker's; to the Superintendent/Competent Person.
- Wearing appropriate clothing and PPE as directed by this plan.
- Completing and signing Appendix D: Employee Acknowledgement Form prior to commencing work.

HEAT-RELATED ILLNESSES: SIGNS, SYMPTOMS & TREATMENT

The following heat-related illnesses are listed in order of severity. All employees, superintendents, subcontractors and installers must be able to recognize the signs of each condition and know the appropriate response.

Any suspected heat stroke requires an immediate call to 911.

Do **NOT** delay emergency services or treatment.

HEAT STROKE – LIFE THREATENING EMERGENCY

CALL 911 IMMEDIATELY. Do NOT attempt to drive the employee to a hospital. Stay with them until EMS arrives.

Signs & Symptoms of Heat Stroke:

- Core body temperature at or above 104°F (You may feel radiating heat on the skin)
- Confusion, disorientation, altered mental status, slurred speech, or irrational behavior.
- Loss of consciousness or fainting.
- Seizures.
- Hot, red, dry skin (classic heat stroke) OR hot, wet skin (exertional heat stroke – common in physically active workers)
- Rapid, strong pulse.
- Absence of sweating despite extreme heat (in classic form).

Treatment of Heat Stroke (While Awaiting EMS):

- **Call 911 immediately.** This is a medical emergency.
- Move the employee to the coolest available area immediately (air-conditioned space is preferred).
- Loose or remove outer clothing and footwear.
- Cool the employee rapidly:
 - Apply ice packs to neck, armpits
 - Wet skin with cool water
 - Fan continuously
- If conscience and able to swallow, offer cool water in small sips.
- Do NOT leave the employee alone at any time.
- Record the time symptoms first appeared and provide to the EMS.

HEAT EXHAUSTION

Heat Exhaustion occurs when the body loses excessive fluid and salt through sweating and is unable to compensate. Left untreated, heat exhaustion can progress into heat stroke.

Signs & Symptoms of Heat Exhaustion:

- Cool, pale, moist skin with heavy sweating.
- Headache, dizziness and/or lightheadedness.
- Nausea, vomiting or stomach cramps.
- Weakness and fatigue.
- Fast, weak pulse.
- Excessive thirst.
- Irritability or mood changes.

Treatment of Heat Exhaustion:

- Move the employee to a cool area immediately (air-conditioned space is preferred).
- Remove unnecessary layers of clothing including PPE, hard hat (if safely permitted), and footwear.
- Have the employee drink cool water or an electrolyte replacement beverage (Gatorade or Pedialyte) in small, frequent sips.
- Apply cool, wet cloths or ice packs to the neck, armpits and forehead.
- Monitor closely. If symptoms do not improve within 30 minutes, or worsen at any time, call 911 immediately and initiate emergency response.
- Send the employee home for the remainder of the shift. Do not allow the employee to return to work that day.
- Document the incident and complete an OSHA-300 entry if recordable.

HEAT CRAMPS

Heat cramps are painful, involuntary muscle spasms caused by dehydration and electrolyte imbalance during physical exertion in hot conditions. They are often an early warning sign of more serious heat illnesses.

Signs & Symptoms of Heat Cramps:

- Painful, involuntary muscle spasms; most commonly in calves, thighs and abdomen.
- Inability to resolve the cramp while stretching.
- Profuse sweating.

Treatment of Heat Cramps:

- Move the employee to a cool, shaded area immediately.
- Encourage the employee to drink cool water and an electrolyte beverage.
- Do not allow the employee to return to strenuous activity for at least 1-2 hours.

- If cramps persist beyond one (1) hour or the employee shows signs of heat exhaustion, transport the employee to an urgent care facility for evaluation.

HEAT SYNCOPE

Heat syncope is a sudden, brief loss of consciousness or dizziness caused by dehydration and prolonged standing in heat. It is common when employees rise quickly from a kneeling or crouching position, which is frequent in finish carpentry and hardware installation.

Signs & Symptoms of Heat Syncope:

- Sudden fainting or near-fainting.
- Dizziness upon standing.
- Pale, moist skin; slow, weak pulse.

Treatment of Heat Syncope:

- Lay the employee flat and elevate legs above heart level.
- Move to a cool area and provide cool water.
- Do not allow the employee to stand quickly.
- Monitor until fully recovered.
- If the employee does not regain consciousness within 1-2 minutes, call 911 for medical intervention.

HEAT RASH

Heat rash (miliaria) occurs when blocked sweat ducts cause inflammation, resulting in clusters of red bumps or blisters. It is particularly common in workers wearing tool belts, knee pads, or other gear that traps moisture against the skin.

Signs & Symptoms of Heat Rash:

- Clusters of small red bumps or clear blisters, typically on the neck, upper chest, waistband area, and inner arms.
- Itching or pickling sensation.

Treatment of Heat Rash:

- Move the employee to a cooler, drier environment when possible.
- Keep the affected area clean and dry.
- Use absorbent powders (not heavy creams that can further block ducts).
- Loosen or remove gear that is trapping moisture against affected skin.
- Apply cool, clean compresses to reduce itching.

INTERIOR HEAT & HUMIDITY HAZARD IDENTIFICATION

Interior finish work for Divisions 06, 08, and 10 on commercial construction sites in Nevada creates heat exposure that often originates indirectly from building systems, materials, and construction activities rather than direct solar radiation. The Designated Person must identify and monitor all heat sources in the work environment at the start of each shift and whenever conditions change.

DIVISION 06: ROUGH & FINISH CARPENTRY/ARCHITECTURAL MILLWORK

- Lack of HVAC during the construction phase routinely causes interior temperatures to exceed outdoor temperatures during the Nevada heat season (May–September), due to the thermal mass of concrete and CMU walls. Interior temperatures of 105–115°F in unconditioned upper-floor spaces are common in Las Vegas, Henderson, and Reno during summer afternoons.
- Radiant heat from concrete slabs, particularly upper floors with rooftop membrane exposure that absorbs intense Nevada solar radiation.
- Low ventilation in enclosed corridors, stairwells, restroom cores, and mechanical rooms where blocking and backing installation occurs.
- Heat generated by extended use of compressors, nailers, saws, and routers in confined or poorly ventilated spaces.
- High humidity from freshly poured concrete, wet plaster/EIFS systems or moisture-laden masonry; elevating the heat index and impairing the body's ability to cool through sweating, even in Nevada's typically arid climate.

DIVISION 08: DOORS, FRAMES, HARDWARE & GLAZING

- Installation of hollow metal door frames in concrete/masonry openings generates physical exertion in often-enclosed, low-airflow spaces.
- Glass curtain wall and storefront glazing on the building envelope expose workers to direct solar radiation even during interior work, particularly on south- and west-facing facades; a significant concern under the high-intensity solar load common in Nevada.
- Overhead glazing installation (skylights, atrium glass) causes radiant heat accumulation from above.
- Mechanical and automatic door installation frequently involves work in vestibules or near exterior openings, exposing workers to significant outdoor heat during Nevada's summer months.
- Hardware installation in mechanical rooms, electrical rooms, and roof-access areas creates confined, high-temperature work conditions.

DIVISION 10: SPECIALTIES

- Toilet partition and restroom accessory installation often occurs in fully enclosed spaces. Early installs may occur without HVAC in service, creating high humidity and heat in tiled or waterproofed restroom cores.
- Signage, lockers, and other accessory installation may involve work in sun-exposed areas (exterior wayfinding signage) or in warm building zones.

- Fire extinguisher cabinet and fire/safety equipment installation frequently occurs in stairwells and mechanical spaces with little ventilation.

MONITORING OF WORKING CONDITIONS

Section 6(2)(c) of R131-24AP requires the Superintendent/Competent Person to monitor working conditions that may create occupational exposure to heat illness. Allegheny Millwork's monitoring approach combines direct measurement, the OSHA Heat Index and ACGIH Wet-Bulb Globe Temperature (WBGT) methodology referred to in NAC 618.

WHAT TO MONITOR

- Air Temperature (Dry Bulb)
- Relative Humidity
- Radiant Heat from Surfaces (concrete slabs, metal decking, glazing): May add 10-15°F equivalent to the perceived heat index.
- Conductive heat from work surfaces (i.e. heated floors, hot equipment)
- Air Movement: whether active ventilation (construction fans, temporary HVAC, open doorways) provides meaningful circulation or is insufficient
- Workload Severity & Duration (light assembly vs. heavy lifting/carrying of millwork panels, door frames, large glazing units increase heat production)
- PPE Burden: tool belts, knee pads, hard hats, full-coverage safety vests and harnesses all increase body heat retention

HOW TO MONITOR

- A calibrated digital thermometer/hygrometer (or combined instrument) shall be used. The Superintendent will record readings at the start of each shift and at midday in each primary work zone whenever conditions identified in the JHA are present, and on every Heat Priority Day (90°F+ outdoor temperature).
- The OSHA-NIOSH Heat Safety Tool app, the OSHA Heat Index Calculator, and the OSHA Outdoor WBGT Calculator are approved reference tools that shall be checked at the start of each shift.
- National Weather Service forecasts and any active heat warning, heat advisory, or excessive heat watch must be reviewed before each shift during the Nevada heat season (May 1 – September 30, or when temperatures consistently exceed 80°F).
- Daily readings, conditions, and any control measures implemented shall be recorded in the project's Heat Monitoring Log and retained per the Recordkeeping section of this plan.

REMOTE/SOLO WORKER MONITORING

If and when an Allegheny Millwork employee, subcontractor or installer must work alone (i.e. a punch-list installer at a remote area of the site), the Superintendent/Competent Person will:

- Establish two-way communication (cell phone or radio) at the start of the shift, confirm fitness for duty, water/cooling availability, work location, and tasks.
- Perform a status check by call or radio every 30 minutes during heat-exposure conditions identified in the JHA.

- If the employee fails to respond, attempt a second contact within 10 minutes; if no response, initiate emergency medical response procedures and dispatch a second person to the location.

POTABLE WATER & HYDRATION REQUIREMENTS

Hydration is the single most important factor in preventing heat-related illness. Section 6(3)(a) of R131-24AP requires provision of potable water as described in 29 CFR 1926.51(a)(1) (with "potable water" defined per 29 CFR 1910.141(a)(2)).

WATER PROVISION

- Clean, cool, potable water will be available to all employees at all times throughout the shift, free of charge.
- Water will be stocked at a minimum of one (1) quart per employee per hour for the duration of the shift, plus a 50% surplus reserve for high-heat days. (This volumetric standard is adopted as a best practice from federal and other state heat-illness programs; Nevada R131-24AP does not specify a numeric volume but requires sufficient potable water consistent with 29 CFR 1926.51.)
- Water containers (coolers, dispensers, or bottled water cases) will be placed within 200 feet of all active work areas. Employees should never have to walk more than one minute to access water.
- Water will be maintained at a cool temperature. Coolers will be stocked with ice at the start of each shift and replenished as needed — particularly important in Nevada's high-temperature climate where uninsulated water rapidly heats.
- Disposable cups or individual water bottles will be provided. Communal open-top containers (buckets) are not permitted, consistent with 29 CFR 1926.51(a)(2).
- Water levels will be checked and replenished when they reach or fall below 50% of initial volume.

HYDRATION GUIDANCE FOR EMPLOYEES

- Do not wait until thirsty to drink. Thirst is already a sign of dehydration. Drink proactively throughout the shift.
- Drink small quantities frequently; approximately four 8-ounce cups (one quart) per hour when working in warm environments.
- During Heat Priority Days (90°F+) or strenuous tasks (carrying millwork panels, framing, setting door frames), increase intake to at least 24 ounces per hour.
- Electrolyte replacement beverages (Gatorade, Pedialyte, Body Armor) are recommended in addition to, not instead of, water when employees are sweating heavily for extended periods. Avoid salt tablets unless directed by a physician.
- Avoid caffeine, alcohol, and heavily sugared beverages during the shift, as these increase dehydration risk.
- Urine color is a quick field indicator: pale yellow indicates adequate hydration; dark yellow/orange indicates dehydration requiring immediate increased fluid intake.

REST BREAKS & COOL-DOWN PERIODS

Section 6(3)(b) of R131-24AP requires the provision of a rest break for any employee who exhibits signs or symptoms of heat illness. NAC 618 Sec. 9.2 further requires that any employee suffering from heat illness, or who believes they need time to recover from the heat to prevent heat illness, must be provided access to an area with shade — or other cooling measure at least as effective as shade — for a period of not less than five (5) minutes.

No employee will be disciplined or discouraged from taking a preventative rest period. Rest breaks for heat-illness recovery are separate from and in addition to regular meal and rest breaks.

REST BREAK SCHEDULE (HEAT-INDEX BASED: BEST PRACTICE)

The schedule below applies the OSHA-NIOSH Heat Index methodology and is adopted as Allegheny Millwork's internal standard. While Nevada R131-24AP does not impose specific thresholds, this schedule ensures consistent field application.

Heat Index (°F)	Recommended Rest Break Frequency	Minimum Duration
Below 80°F	As Needed/Requested	5 Minutes
80°F – 90°F	Every 2 Hours (Encouraged)	5 Minutes
90°F – 103°F (Heat Priority)	Every 1 Hour	10 Minutes
103°F – 115°F	Every 45 Minutes	10 Minutes
Above 115°F	Every 30 Minutes (Mandatory)	15 Minutes

REST BREAK REQUIREMENTS

- Rest breaks will take place in the designated cooling area (see next section), which must be cooler than the active work area and shielded from radiant-heat sources.
- Employees may request a preventative rest period at any time without fear of reprisal.
- Water and electrolyte drinks will be available at the cooling area at all times.
- Any employee on a rest break will be monitored by the Superintendent / Designated Person for signs of heat illness.
- Any employee displaying heat-illness symptoms during a rest break will receive immediate first aid and will not return to work until medically cleared.
- Rest breaks taken to recover from or prevent heat illness do not count against regular meal or rest breaks, and no employee will be disciplined for taking one.

MEANS OF COOLING: INTERIOR WORK

Because Allegheny Millwork's scope is primarily interior finish work, shade from direct sunlight is not the primary cooling concern; ventilation, air movement, and temperature management of the interior workspace are the priority. Section 6(3)(c) of R131-24AP requires the provision of means of cooling for employees, and Section 6(3)(e) requires identification and mitigation of any work process that may generate additional heat or humidity.

PREFERRED COOLING METHODS (HIERARCHY)

- **Air Conditioning (Engineering Control - Preferred)**: When an air-conditioned space exists on the project (GC office trailer, completed and mechanically conditioned portion of the building, or rented portable HVAC unit), it will be designated as the primary cooling area and communicated to all employees.
- **Mechanical Ventilation**: When A/C is not available, high-volume low-speed (HVLS) fans, barrel fans, or air movers will be deployed in active work areas to maintain air circulation. A minimum of one fan per 2,000 sq. ft. of active interior work area is recommended.
- **Portable Evaporative Coolers (Swamp Coolers)**: Highly effective in Nevada's typically low-humidity climate. Note: evaporative cooling becomes less effective when relative humidity exceeds approximately 60% and should not be relied upon during humid conditions (e.g., immediately after concrete pours or rain events).
- **Misting Fans**: Portable misting fans can be deployed in non-finish areas. *Note: misting must not be used near millwork, wood doors, cabinetry, or other moisture-sensitive substrates.*
- **Cross-Ventilation**: Whenever safe and permitted by the GC, opposite building openings (doors, windows, temporary openings) will be utilized to create passive cross-ventilation.
- **Reflective Shielding**: Reflective barriers, foil-faced insulation, or temporary curtains will be used to block radiant heat from glazing on south- and west-facing facades during extreme heat.

COOLING AREA REQUIREMENTS

- A designated cooling/rest area must be identified and communicated to all employees at the start of every shift.
- The cooling area must be at a temperature meaningfully cooler than the active work area and shielded from radiant-heat sources.
- The cooling area must be large enough to accommodate all employees simultaneously if necessary.
- The cooling area must be equipped with seating, water supply, and a basic first-aid kit.
- The Designated Person will verify the cooling area is functional (fans running, A/C operating, water stocked) before the shift begins.
- Per NAC 618 Sec. 9.2, where shade or air-conditioned space is impractical, an alternative cooling measure (such as fans or water-mist devices) may be used if the employer can demonstrate it is at least as effective as shade in allowing the employee to cool.

COORDINATION WITH THE GENERAL CONTRACTOR

- The Superintendent will communicate with the GC daily regarding the HVAC commissioning schedule and anticipated availability of conditioned air in work zones.
- When work must proceed in unconditioned spaces, the Superintendent will deploy the engineering and administrative controls in the hierarchy above and update the Heat Monitoring Log.
- The Superintendent will request that the GC maintain at least one ventilated or accessible building entry/egress point in each major work zone for cooling purposes.

ACCLIMATIZATION SCHEDULE

Acclimatization is the physiological process by which the body adapts to working in hot environments. A properly acclimatized worker produces more sweat sooner, maintains a lower core temperature, and recovers faster. The vast majority of heat-related fatalities in construction occur within the first week of heat exposure.

Nevada OSHA's January 29, 2025 guidance recommends a 7-to-14-day staggered acclimatization for new workers, beginning at 20% of normal workload and time in the hot environment. For workers returning from an absence of three or more days, acclimatization should begin at 50% of normal workload, staged over three consecutive days.

ACCLIMATIZATION SCHEDULE

Day	New Employee (Max Heat Exposure)	Returning Employee (Max Heat Exposure)	Notes
1	20%	50%	Assign Light Tasks Frequent Monitoring
2	40%	60%	Increase Workload Gradually
3	60%	80%	Continue Monitoring
4	80%	100%	Never Full Capacity
5	100%	100%	Full Capacity With Monitoring
6-14	100%	100%	Full Capacity New Employee Observed Through Day 14

ACCLIMATIZATION POLICIES

- New employees will not be assigned full-intensity physical tasks (carrying millwork panels, setting hollow metal frames, large-pane glazing) during their acclimatization period without confirmed physical acclimatization. The Superintendent/Competent Person must closely observe them throughout this period.
- Employees returning from absences of three (3) or more consecutive days will follow the Returning Employee schedule above.
- Employees transferring from cooler climates or transitioning from air-conditioned office/shop environments to active jobsite work, will follow the New Employee schedule.
- During a heat wave (any day when the predicted high is at least 80°F and at least 10°F higher than the average high for the preceding five days), all employees, regardless of prior acclimatization, must be closely observed by the Superintendent/Competent Person.

- Physical fitness, age, medication use, pregnancy, fever, gastrointestinal illness, heart disease, obesity and prior heat-illness history will be considered in individual acclimatization plans by the Superintendent in consultation with Human Resources, as appropriate.
- Per Nevada OSHA guidance, employees will be advised that the following medications can increase heat-stress risk: amphetamines (including ADHD medications), diuretics, antihypertensives, anticholinergics (including some COPD medications) and antihistamines. Employees with concerns should consult their physician or pharmacist.

HEAT PRIORITY DAY PROCEDURES (90°F+)

In accordance with Nevada OSHA's May 4, 2022 guidance under the Heat Illness National Emphasis Program, any day on which the temperature reaches or is forecast to reach 90°F is treated as a Heat Priority Day. The procedures below apply in addition to baseline heat-illness prevention protocols and will be implemented before and during high-heat conditions.

HEAT PRIORITY DAY ACTIVATION

Heat Priority Day procedures activate when ANY of the following are true:

- Outdoor temperature reaches or is forecasted to reach 90°F
- Indoor heat index reaches or exceeds 90°F in any active work area
- The National Weather Service (NWS) has issued an Excessive Heat Watch, Heat Advisory or Excessive Heat Warning for the project area
- Outdoor temperature reaches 90°F AND interior HVAC is non-functional or inadequate.
- The Superintendent/Competent Person determines that conditions pose elevated risk based on task, workforce or environmental factors

HEAT PRIORITY DAY REQUIREMENTS

- **Pre-Shift Safety Meeting (Mandatory):** Conducted by the Designated Person, covering the day's forecast and current heat index, heat-illness recognition, the rest-break schedule, water locations, the cooling area location, and emergency procedures.
- **Effective Communication:** The Designated Person personally verifies water-supply levels, cooling-area functionality, and communication-device operability before any worker begins.
- **Buddy System (Mandatory):** All employees will be paired. No employee may work alone in Heat Priority conditions, particularly in enclosed or low-airflow spaces. Any solo work that cannot be eliminated must be covered by the remote-monitoring protocol in the Monitoring section.
- **Mandatory Observation Checks:** The Superintendent/Competent Person will visually check in with each employee or pair at least once every thirty (30) minutes.
- **Hydration Reminder:** Each employee will be reminded to consume a minimum of eight (8) ounces of water every 15–20 minutes, aiming for at least one quart per hour.
- **Task Reassignment:** Physically intensive tasks (heavy millwork carrying, overhead installation, framing) will be rescheduled to early morning where possible, or additional employees assigned to reduce individual exertion.
- **Shift Duration:** May be shortened at the Superintendent's discretion or per GC directive when conditions present unacceptable risk.
- **Symptom-Based Removal:** Any employee who reports not feeling well, regardless of whether heat illness is clearly the cause, will be removed from the heat environment immediately and evaluated.

OUTDOOR & DELIVERY EXPOSURE PROCEDURES

Although Allegheny Millwork's primary scope is interior finish work, employees are exposed to outdoor heat during material deliveries, equipment offloading, staging area setup, and transit between site entry and interior work areas. Nevada's outdoor environment; particularly in the Las Vegas Valley, Henderson, North Las Vegas, Boulder City, and the Mojave/Great Basin transition zones, produces some of the most extreme outdoor heat-stress conditions in the United States, with summer afternoon highs frequently exceeding 105°F and surface temperatures (asphalt, concrete, metal) routinely exceeding 140°F.

OUTDOOR EXPOSURE ASSESSMENT

- The Superintendent/Competent Person will assess the current and forecast outdoor heat index before any outdoor work begins each day. Resources include the National Weather Service (weather.gov), the OSHA-NIOSH Heat Safety Tool app, the OSHA Heat Index Calculator, and the OSHA Outdoor WBGT Calculator.
- Deliveries will be scheduled, when feasible, for early morning (before 10:00 AM) or late afternoon/evening (after 5:00 PM) to minimize exposure during peak heat hours, which in Nevada typically run from 1:00 PM to 6:00 PM during summer.
- Duration of outdoor exposure should be minimized. No individual employee should be required to remain outdoors in direct sunlight for more than thirty (30) consecutive minutes when the outdoor heat index exceeds 103°F without a mandatory indoor cooling break.

DELIVERY & OFFLOADING PROCEDURES

- A minimum of two employees will be assigned to all delivery/offloading tasks to allow rotation and mutual monitoring.
- Shade Access: Sufficient shade will be provided and maintained during outdoor operations so employees can sit in a normal posture fully in the shade without touching each other. A shaded staging area (canopy, pop-up, building overhang, or conditioned delivery area) will be established whenever outdoor work exceeds thirty (30) minutes during the Nevada heat season. NAC 618 Sec. 9.2 permits cooling alternatives at least as effective as shade (such as fans or water-mist devices) where shade is impractical.
- Cool, potable water will be accessible within fifty (50) feet of the outdoor work area during any delivery or offloading activity.
- Employees will not wear non-breathable PPE (full-cover Tyvek, impermeable coveralls) during outdoor work in heat conditions above 91°F H.I. without additional monitoring and shortened outdoor exposure durations.
- Employees returning indoors after outdoor exposure will take a 5-10 minute cooling break to normalize body temperature before resuming finish work tasks.

OUTDOOR HEAT INDEX THRESHOLDS & ACTIONS

The thresholds below are adopted as Allegheny Millwork's internal best practice standard, drawing on OSHA Technical Manual Section III Chapter 4 (Heat Stress), the OSHA-NIOSH Heat Safety Tool and ANSI/ASSP A10.50-2024. They go beyond Nevada R131-24AP's performance-based requirements and provide concrete field guidance for Nevada conditions.

Risk Level	Heat Index	Required Actions
LOW	< 80°F	• Standard Hydration • Provide Water • Monitor Employees
CAUTION	80°F – 90°F	• Shade & Cool Drinking Water Available • Encourage Rest Breaks • Observe New Employees During Acclimatization
MODERATE	90°F – 103°F	• Heat Priority Day Procedures Active • Mandatory Buddy System • Rest Breaks Every 1 Hour • Reduce Strenuous Outdoor Tasks • Verify Communication & Water Supply at Start of Shift
HIGH	103°F – 115°F	• Limit Outdoor Exposure to 30 Min. Max Per Stretch • Mandatory Buddy System • Rest Breaks Every 45 Minutes • Observation Checks Every 30 Minutes • Consider Rescheduling Deliveries
VERY HIGH	115°F – 129°F	• Minimize Outdoor Work to Essential Delivery/Emergency Only • Rotate Employees Every 15-20 Minutes Outdoors • Emergency Action Plan Ready & Reviewed
EXTREME	> 129°F	• SUSPEND Non-Essential Outdoor Work • Reschedule Deliveries • Only Emergency Operations with Full Precautions

Heat Index values reference the National Weather Service Heat Index. In direct sun, add approximately 15°F to the Heat Index when assessing apparent temperature for workers without shade.

WORK CLOTHING & PERSONAL PROTECTIVE EQUIPMENT (PPE)

Appropriate clothing and PPE selection is especially important for interior finish trade workers in Nevada's climate, where both heat retention from enclosed spaces and incidental outdoor exposure must be balanced against jobsite safety requirements. Section 6(3)(c) of R131-24AP recognizes PPE-based cooling as one means of control; Nevada OSHA's January 29, 2025 guidance specifically endorses cooling vests, hats, and reflective garments.

CLOTHING GUIDANCE

- Base layer clothing should be lightweight, moisture-wicking & breathable. Synthetic performance fabrics or light cotton are preferred.
- Light-colored clothing is preferred to reduce radiant heat absorption when outdoors or in glass-adjacent work zones, particularly important under Nevada's high-intensity solar radiation.
- Long-sleeved shirts with UPF/UV protection are recommended for outdoor deliveries and glazing work. Short sleeves are acceptable for most interior work where sun exposure is limited.
- Clothing must allow sufficient range of motion for finish carpentry, hardware installation, and millwork tasks. Avoid overly loose garments when working near powered cutting equipment.
- Shorts are permitted for interior work when no safety hazard exists, subject to GC site rules. Knee pads should be used with shorts for kneeling tasks to protect skin.

PPE CONSIDERATIONS FOR HEAT

- **Hard Hats:** Vented hard hats are preferred for Nevada heat conditions. Standard hard hats create a heat-trapping effect and should be supplemented with a moisture-wicking hard-hat liner. Wide-brim sun shields may be added for outdoor work.
- **High-Visibility Vests:** Lightweight mesh safety vests are required where mandated by the GC. Full-coverage solid vests significantly increase heat burden and should be replaced with mesh whenever site rules permit.
- **Knee Pads:** Prolonged wear in hot conditions traps moisture and heat. Employees should remove knee pads during rest breaks.
- **Tool Belts & Body Harnesses:** These items significantly increase heat retention. Employees in full body harnesses during Heat Priority Days will receive additional rest breaks and observation checks.
- **Gloves:** Lightweight, breathable work gloves are preferred. Latex-coated or heavy leather gloves significantly reduce hand cooling.
- **Cooling Vests:** Per Nevada OSHA's January 29, 2025 guidance, cooling vests and water-cooled/dampened garments may be used and are particularly effective in Nevada's low-humidity conditions. Note that cooling vests can become insulators once they reach body temperature; recharge or replace as designed.
- **Sunscreen:** SPF 30 or higher should be applied to all exposed skin for any outdoor work. Sunscreen will be made available by Allegheny Millwork at no cost during the heat season.
- Wide-brimmed hard-hat sun shields are recommended for outdoor delivery and staging work.

MEDICAL EMERGENCY RESPONSE PROCEDURES

All Allegheny Millwork employees, subcontractors, and installers must be familiar with emergency response procedures and capable of initiating them. Section 6(2) of R131-24AP requires the Superintendent/Competent Person, when an employee is experiencing signs or symptoms of heat illness requiring an emergency response, to:

1. Contact emergency medical services (or ensure EMS is contacted)
2. Provide all information necessary to enable EMS to reach the employee, including contact information and directions
3. Ensure the employee is, if necessary, transported to a location where EMS can reach them. The employer's responsibility ends when EMS makes physical contact with the employee.

PRE-SHIFT EMERGENCY PREPAREDNESS

- The Superintendent will verify that a charged, functional cell phone or two-way radio is available and will remain on their person throughout the shift. Cell-service reliability in the work area must be confirmed; if unreliable, a secondary means of communication (radio, satellite messenger) must be established.
- All employees will be informed of the address and nearest cross streets of the jobsite at the start of the first day, and again whenever the crew is working at a new floor level or area with a different site-access point.
- The address and turn-by-turn directions to the nearest emergency room and the nearest urgent care facility will be posted in the cooling/break area and saved in the Superintendent/Competent Person's phone.
- A first-aid kit stocked with cold packs, bandages, and basic supplies will be maintained in the cooling area and in the Superintendent's vehicle.
- On every Heat Priority Day, the Superintendent/Competent Person will perform a tabletop walkthrough of the steps below at the pre-shift meeting.

EMERGENCY RESPONSE STEPS

Step	Action
1	IDENTIFY: Recognize that an employee is experiencing a heat-related illness. When in doubt, assume the worst-case scenario and act accordingly.
2	CALL 911: For any suspected heat stroke, loss of consciousness, seizure or severely altered mental status, call 911 immediately. Do not delay.
3	NOTIFY: Alert the Superintendent/Competent Person and the General Contractor Site Superintendent immediately.
4	PROVIDE EMS REACH INFO: As required by R131-24AP §6(2)(a), the Superintendent/Competent Person provides EMS with all information necessary to reach the employee. Site address, gate access, building, floor & a meeting point, and dispatches an employee to meet EMS at the site entrance.
5	COOL: Move the employee to the coolest location available. Apply cool water/cold packs to neck, armpits & groin and fan continuously.
6	STAY: Do not leave the employee unattended under any circumstances. Maintain observation until EMW arrives or the employee is transported.
7	TRANSPORT IF NEEDED: Per R131-24AP §6(2)(a)(3), if necessary and appropriate, the employee will be transported to a location where EMS can reach them. Do not allow a heat-illness employee to drive themselves. For mild symptoms (cramps, rash) only, transport to an urgent care facility may be arranged with a second employee accompanying them.
8	DOCUMENT: Record the time symptoms were first observed, what actions were taken and the employee's condition at each step. Provide this to EMS on arrival.
9	COMMUNICATE: Notify Human Resources and management as soon as the situation has stabilized.
10	REPORT: Per Nevada AB 54 (NRS 618.378) and 29 CFR 1904, any work-related fatality must be orally reported to Nevada OSHA within eight (8) hours, and any inpatient hospitalization, amputation or loss of an eye must be reported within twenty-four (24) hours. <u>Las Vegas:</u> 702-476-9020 <u>Reno:</u> 775-688-3700
11	INVESTIGATE: Within twenty-four (24) hours, conduct a preliminary incident review. Per NAC 618.540, the JHA must be reviewed and revised if necessary, following any accident.

RECORDKEEPING AFTER INCIDENT

- All heat-related illness incidents will be evaluated for OSHA-300 Log recordability (criteria: days away from work, restricted work, medical treatment beyond first aid, loss of consciousness, or significant injury/illness diagnosed by a healthcare professional).
- A written incident report will be completed within 24 hours and retained in the project file.
- The Job Hazard Analysis and Heat Illness Prevention Plan will be reviewed under NAC 618.540 after any incident to identify and implement corrective actions.
- Per Nevada AB 54 (NRS 618.378): work-related fatalities must be reported orally to Nevada OSHA within 8 hours; inpatient hospitalizations, amputations, or loss of an eye must be reported within 24 hours.

TRAINING

Section 7 of R131-24AP requires employers to provide a training program for each employee in a job classification identified in the JHA, and for the Designated Person. Training must enable each employee to recognize the hazards of heat illness and to follow the procedures for minimizing those hazards. Training must be completed before performing work duties. While R131-24AP does not impose annual retraining, Nevada OSHA's January 29, 2025 guidance identifies annual refresher training as a best practice; Allegheny Millwork adopts that best practice.

TRAINING REQUIREMENTS BY ROLE

All Employees, Subcontractors & Installers (in JHA Identified Classifications)

- Causes and risk factors for heat illness, with emphasis on interior construction environments (environmental and personal risk factors, including medications and medical conditions).
- Signs and symptoms of heat stroke, heat exhaustion, heat cramps, heat syncope, and heat rash; awareness that heat illness can progress quickly from mild to life-threatening.
- Importance of frequent consumption of small quantities of water (up to four 8-oz cups per hour); what to drink and what to avoid.
- How to find and use the designated cooling/rest areas on each specific project.
- The Buddy System and how to monitor coworkers for heat-illness signs.
- Steps to take when a coworker shows signs of heat illness, and the importance of immediately reporting symptoms.
- How to contact the Superintendent/Competent Person and Emergency Services.
- The right to take a preventative rest period at any time without fear of retaliation, as required by NAC 618 Sec. 9.2.
- Acclimatization: the concept, importance, and methods, including what to expect during the first 7-14 days on the jobsite.
- How to recognize National Weather Service heat alerts and what they mean for the day's work.

Superintendent/Competent Person: Additional Training

- 24AP, NRS 618.375, and NRS 618.383.
- How to conduct, review, and revise a Job Hazard Analysis under R131-24AP §5 and NAC 618.540.
- How to measure and interpret heat-stress readings using calibrated thermometer/hygrometer, OSHA-NIOSH Heat Safety Tool, OSHA Heat Index Calculator, and OSHA Outdoor WBGT Calculator.
- Identifying interior heat hazards specific to Divisions 06, 08, and 10 work scopes.
- How to implement acclimatization schedules and closely observe new employees during their first 14 days on the jobsite.
- How to conduct pre-shift safety meetings on Heat Priority Days.
- Emergency first-aid procedures, including how to rapidly cool a heat-stroke victim while awaiting EMS.

- Emergency response duties under R131-24AP §6(2): contacting EMS, providing reach-information, and arranging transport when needed.
- How to complete incident documentation, OSHA-300 Log entries, Nevada-required oral reports of fatalities/hospitalizations/amputations to Nevada OSHA, and the project Heat Monitoring Log.
- How to monitor remote/solo workers and respond to a missed status check.

TRAINING DELIVERY

- Initial training will be completed before the employee's first day on any project site where heat exposure exists, as required by NAC 618.540.
- Training will be available in both English and Spanish (and additional languages as needed) and will be conducted in the employee's primary language.
- Training methods include:
 - illustrated presentation
 - jobsite toolbox talks
 - video-based instruction, and interactive Q&A sessions
 - Free training is also available through:
 - Nevada SCATS at 1-877-472-3368 or 4safenv.state.nv.us.
- All training must include an opportunity for employees to ask questions and receive answers in a language they understand.
- Refresher training will be conducted at the start of each Nevada heat season (May 1, or when temperatures first consistently exceed 80°F at the project site).
- Additional training will be conducted whenever: an incident occurs; this plan is updated; new hazards are identified; an employee is observed not following the plan; or a JHA is revised due to materially changed tasks.
- Training records, including topic, date, trainer, and signed attendance sheet, will be retained for three (3) years (OSHA-300 Log retained for five (5) years per 29 CFR 1904.33).

PROGRAM REVIEW & RECORDKEEPING

PLAN REVIEW SCHEDULE

- Annually, no later than April 1 of each year, prior to the Nevada heat season.
- Whenever Nevada OSHA, federal OSHA, or NIOSH issues new or updated requirements or guidance affecting heat illness.
- Following any heat-related illness incident on a company project (NAC 618.540 — accident review).
- When a task for a job materially changes (R131-24AP §5).
- When new Division 06, 08, or 10 work scopes are added that introduce new heat-hazard profiles.
- Based on employee, supervisor, or Nevada OSHA / SCATS feedback identifying plan deficiencies.

RECORDS TO BE MAINTAINED (3 YEAR RETENTION STANDARD)

Record Type	Retention Requirement
Job Hazard Analysis (JHA): Original & Revisions	Throughout the active life of the JHA, plus three (3) years. Available to Nevada OSHA on Inspection
Training Course Records & Signed Attendance Sheets	Three (3) Years from Date of Training
Employee Acknowledgement Forms (Appendix D)	Three (3) Years. Active Employees Retrained Throughout Employment
Daily Heat Monitoring Log (Interior Temperature & Relative Humidity)	Three (3) Years Per Project
Heat-Related Illness Incident Reports	Three (3) Years. OSHA-300 Log Retained for Five (5) Years Per 29 CFR 1904.33
Heat Illness Prevention Plan (All Versions)	Three (3) Years. Current Version Always on Project Site & Available to Employees & Nevada OSHA Representative
Corrective Action Reports Following Incidents (NAC 618.540)	Three (3) Years
Acclimatization Records for New & Returning Employees	Three (3) Years
Designation of Superintendent/ Competent Person & Designee	Throughout Active Designation + Three (3) Years

All records will be maintained in the project file (electronic and/or paper) and at Allegheny Millwork's main office. The current version of this Heat Illness Prevention Plan will always be available at the project site, in English & Spanish (and additional languages as needed) and accessible to all employees and to Nevada OSHA representatives upon request.