

ALLEGHENY MILLWORK

HURRICANE PREPAREDNESS PLAN & CHECKLIST

Interior Finish Trades – Division 06: Rough & Finish
Carpentry/Architectural Millwork

Finish Carpentry | Architectural Millwork | Casework | Paneling | Interior Doors | Plastic & Composite Fabrications

Project Name & Number:	
Project Address:	
General Contractor:	
Plan Prepared By:	
Date Issued:	
Revision/Version:	

HURRICANE PREPAREDNESS PLAN & CHECKLIST

TABLE OF CONTENTS

Purpose & Scope.....	3
Applicable Division 06 Scope Sections	3
Interior Trades Risk Profile	4
Definitions	5
Plan Activation & Alert Levels	8
Roles & Responsibilities.....	9
Project Manager	9
Millwork Installation Lead	9
Superintendent/Site Safety Coordinator	9
Environmental Control Lead	9
Material Control/Warehouse Lead.....	10
Interior Trades Vulnerability Analysis	11
Moisture Intolerance by Product	11
Environmental Thresholds	11
Material Specific Protection Measures	12
Architectural Woodwork in Interior Storage	12
Architectural Woodwork & Plastic Laminate Casework.....	12
Wood Paneling (Flush, Stile & Rail, Ornamental).....	13
Wood Stairs, Railing & Standing/Running Trim.....	13
Architectural Wood Doors & Wood Frames	13
Interior Plastic Fabrications & Composites	14
Environmental Control During & After the Event	14
Building Envelope Coordination.....	15
Building Status Classifications.....	15
Personnel Safety & Demobilizations	16
Documentation & Insurance Requirements	16
Post Event Assessment & Recovery	17
Initial Damage Assessment (First 24 Hours)	17
Material Disposition	17
Drying & Environmental Restoration.....	17
Pre-Season Checklist (Level 1)	Checklist A
72 – 96 Hour Checklist (Level 2: Watch Issued)	Checklist B
36 – 48 Hour Checklist (Level 3: Warning issued)	Checklist C
Post-Event Checklist (Level 4: All Clear).....	Checklist D
Emergency Contact Roster	Appendix A

Protection Material Inventory	Appendix B
Plan Approval & Distribution	Appendix C

PURPOSE & SCOPE

This Hurricane Preparedness Plan establishes the procedures, responsibilities and protective measures that Allegheny Millwork is required to safeguard personnel, architectural millwork, casework, interior finishes and installed interior work from the effects of a tropical storm or hurricane. This plan applies to all work performed under CSI MasterFormat Division 06 Interior Trades scopes.

This plan is intended to comply with all federal, state and local regulations including OSHA 29 CFR 1926 (Construction Industry Standards), NFPA 1600 (Standard on Continuity, Emergency and Crisis Management), the International Building Code (IBC) as adopted locally, FEMA guidance for construction sites in hurricane prone regions, the AWI Quality Standards for Architectural Millwork and the project's governing contract documents, specifications and General Conditions.

Division 06 interior trade materials, including architectural millwork, AWI-Grade casework, wood paneling, stairwork, interior trim, architectural doors, plastic laminate, solid surface and composite fabrications, are uniquely vulnerable to moisture intrusion, environmental excursions and debris impact that accompany a hurricane event. Unlike structural framing, many of these products cannot be salvaged once wetted and represent significant schedule and cost implications. This plan addresses those specific vulnerabilities.

APPLICABLE DIVISION 06 INTERIOR TRADE SCOPE SECTIONS

- 06 20 00: Finish Carpentry
 - Interior Trim
 - Running & Standing Trim
 - Millwork Installation
- 06 22 00: Millwork
 - Shop-Fabricated Interior Woodwork
- 06 25 00: Prefinished Paneling
- 06 26 00: Board Paneling
- 06 40 00: Architectural Millwork
 - AWI/AWS Premium, Custom & Economy Grade
- 06 41 00: Architectural Wood Casework
- 06 42 00: Wood Paneling
 - Flush
 - Stile-and-Rail
 - Ornamental
- 06 43 00: Wood Stairs & Railings
- 06 44 00: Ornamental Woodwork
- 06 46 00: Wood Trim
- 06 48 00: Wood Frames
 - Architectural Wood Door Frames
- 06 49 00: Wood Screens & Shutters

- Interior Applications
- 06 60 00: Plastic Fabrications
 - Solid Surface
 - FRP
 - Acrylic
 - PVC – Interior Applications
- 06 61 00: Simulated Stone Fabrications
 - Interior Surfaces
- 06 64 00: Plastic Paneling
 - Interior Applications
- 06 65 00: Plastic Simulated Wood Trim
 - Interior Applications
- 06 66 00: Custom Ornamental Simulated Woodwork

INTERIOR TRADES RISK PROFILE

Interior trades are typically installed late in the project schedule, in areas that are expected to be weathertight. A hurricane event can compromise that assumption through:

- **Envelope Breach**: Wind-borne debris penetrating glazing or damaging roofing allows direct water intrusion into finished spaces
- **Moisture Migration**: Wind-driven rain forced past nominally weather resistant assemblies saturates wall cavities and floor structures from above
- **Environmental Excursion**: Power loss eliminates HVAC conditioning, humidity can exceed 80% for days, causing veneer delamination, panel warping and finish blush
- **Storm Surge**: Coastal projects may experience flood intrusion through ground-floor openings regardless of building weather tightness
- **Post-Event Mold**: Wetted assemblies not dried within 48-72 hours typically develop biological growth requiring selective demolition

DEFINITIONS

The following definitions apply to various terms used within this document.

Condition of Readiness (COR): The five (5) conditions are defined below.

Condition V: Destructive winds are possible in geographic proximity to Allegheny Millwork projects or jobsites within 96 hours. Normal jobsite cleanup and good housekeeping practices should be followed.

Condition IV: Destructive winds are possible in geographic proximity to Allegheny Millwork projects or jobsites within 72 hours. Normal daily jobsite cleanup and good housekeeping practices should be followed. Collect and store in piles or containers, scrap lumber, waste material and rubbish for removal and disposal at the end of each workday. Maintain the jobsite including storage areas, free of accumulation of debris. Stack paneling, blocking, trim and other millwork materials into neat piles less than four (4) feet high. Protect millwork with plastic/poly sheeting, moving blankets and label. Remove all trash debris and other objects which could become a missile hazard. Contact General Contractor for Condition requirements, updates and completion of required actions.

Condition III: Destructive winds are possible in geographic proximity to Allegheny Millwork jobsites within 48 hours. Maintain Condition IV requirements. Begin securing equipment, materials and the jobsite and taking actions necessary for Condition I, which cannot be completed within 18 hours. Cease all routine activities that might interfere with securing operations. Begin collecting and stowing all gear and portal equipment. Make preparations for securing buildings. Review requirements pertain to Condition II and continue action as necessary to attain Condition III readiness.

Condition II: Destructive winds are possible in geographic proximity to Allegheny Millwork jobsites within 24 hours. Curtail or cease routine activities until securing operations are complete. Reinforce or remove form work and scaffolding. Secure machinery, tools, equipment and materials or remove from jobsite. Expend every effort to clear all missile hazards and loose equipment from the jobsite. Monitor weather channels and completion of required actions.

Condition I: Destructive winds are possible in geographic proximity of Allegheny Millwork jobsites within 12 hours. Perform and complete all remaining actions required for lower conditions of readiness. Secure the jobsite and leave the premises.

Destructive Winds: Generally winds reaching or exceeding the force of a tropical storm (≥ 39 mph or 34 knots). Winds from any storm system (tropical or otherwise) that are determined to have the potential to cause property damage or personal injury that would warrant Allegheny Millwork jobsites to initiate a Condition IV alert.

Hurricane Watch: an announcement for specific areas where a hurricane or an incipient hurricane poses a possible threat to a coastal area, generally within 36 hours.

Hurricane Warning: A warning that sustained winds of 74 mph (64 knots) or higher, associated with a hurricane are expected in a specified coastal area in 24 hours or less.

Hurricane: A tropical cyclone in which the maximum sustained surface wind is 74 mph (64 knots) or greater.

Missile Hazard: Any object that may become airborne during high winds.

Severe Weather: Any storm of tropical or non-tropical origin that has the capacity to produce destructive winds.

Storm Surge: An abnormal rise in seas level accompanying a hurricane or other intense storm, and whose height is the difference between the observed level of the sea surface and the level that would have occurred in the absence of the storm.

Storm Tide: The actual sea level resulting from the astronomical tide combined with the storm surge. This term is used interchangeably with “Hurricane Tide”.

Tropical Depression: A tropical low-pressure system in which the maximum sustained surface wind is 38 mph (38 knots) or less.

Tropical Storm: A tropical low-pressure system in which the maximum surface wind ranges from 39 – 73 mph (34 – 63 mph) inclusive. This is the strength at which the National Hurricane Center applies a name to the storm.

Tropical Storm Watch: Tropical storm conditions pose a threat to a coastal area generally within 36 hours.

Tropical Storm Warning: A warning for tropical storm conditions with sustained winds within the range of 39 – 73 mph which are expected in a specified coastal area within 24 hours or less.

PLAN ACTIVATION & ALERT LEVELS

Allegheny Millwork's activation of this plan shall be tied to official advisories issued by the National Hurricane Center (NHC) and the National Weather Service (NWS) for the jobsite. The following four tier alert system shall govern Allegheny Millwork's interior trade actions.

Alert Level	Trigger	Timeframe to Impact	Primary Interior Trades Action
Level 1: Season Watch	Atlantic Hurricane Season Begins (June 1 st) OR a Named Storm has formed in the Basin	Pre-Season/5+ Days	• Verify Plan, Inventory & Supplies • Confirm Shop-Storage Arrangements with Millwork Supplier
Level 2: Advisory	Tropical Storm or Hurricane Watch Issued for the Region	72 – 96 Hours	• Hold New Millwork Deliveries • Relocate Staged Millwork to Building Core • Stage Protection Materials
Level 3: Warning	Hurricane Warning Issued for Jobsite Location	36 – 48 Hours	• Cover Installed Millwork • Verify Envelope Continuity • Secure Conditioning • Demobilize Personnel
Level 4: All Clear	Storm has Passed; Local Authorities Authorize Re-Entry	Post-Event	• Environmental Assessment • Moisture Testing • Material Disposition • Phased Resumption

ROLES & RESPONSIBILITIES

The following positions hold specific duties under this plan. Names and contact information shall be recorded in Appendix A: Emergency Contact Roster at the end of this Plan.

PROJECT MANAGER

- Overall responsibility for plan execution within Allegheny Millwork's scope of work
- Coordinates with General Contractor's Site Superintendent, Safety Officer and Division 07 and Division 08 building envelope trades
- Authorizes stop-work, protection deployment and demobilization decisions
- Documents all preparedness actions with photographs and written log
- Serves as primary point of contact with the architectural millwork supplier

MILLWORK INSTALLATION LEAD

- Maintains the inventory of onsite architectural millwork, casework and paneling with location and value
- Directs the relocation of staged millwork to designated interior dry storage
- Executes coverage and protection of installed millwork per Material Specific Protection Measures section
- Documents pre-event condition of all items with photographs keyed to shop-drawing references

SITE SAFETY COORDINATOR

- Monitors NHC/NWS advisories and communicates alert level changes
- Verifies PPE inventory and rain/wind gear for the all Allegheny Millwork employees and installers
- Conducts pre-storm toolbox talk safety briefing
- Accounts for all Allegheny Millwork employees, subcontractor, supplier and installer personnel at demobilization

ENVIRONMENTAL CONTROL LEAD

- Monitors interior relative humidity and temperature in rooms containing installed or staged millwork
- Coordinates with General Contractor and MEP trades for temporary conditioning before, during (where feasible) and after the event
- Maintains environmental data logger records for all affected rooms
- Coordinates post-event drying protocol with IICRC-Certified Restoration vendor

MATERIAL CONTROL/WAREHOUSE LEAD

- Maintains inventory or shop-stored versus onsite interior trade materials
- Coordinates with suppliers to suspend deliveries during alert periods
- Documents condition of all material packaging and labeling before and after the event

INTERIOR TRADES VULNERABILITY ANALYSIS

Allegheny Millwork bases every decision in this plan based on the understanding of how each product fails. The following analysis drives the necessary protection measures in the Material Specific Protection Measures section.

MOISTURE INTOLERANCE BY PRODUCT

Product	Moisture Intolerance	Failure Mode	Salvageable?
Veneer Paneling (AWI)	Very Low	Delamination Telegraphing	No
Wood Casework (Veneer)	Very Low	Delamination Warping	Rarely
Plastic Laminate Casework	Low	Edge Delamination	Sometimes
Architectural Wood Doors	Very Low	Warping Veneer Separation	No
Solid Wood Trim	Moderate	Swelling Cupping	Yes, If Dried Quickly
Stairwork (Treads, Rails)	Low	Warp Finish Blush	Rarely
Solid Surface	High	Impact Fracture Only	Usually
FRP Panels (Installed)	High	Adhesive Failures	Sometimes
PVC/Composite Trim	High	Thermal Distortion Only	Usually
MDF Core Millwork	Very Low	Swelling Disintegration	No

ENVIRONMENTAL THRESHOLDS

AWI Section 2 requires that architectural woodwork be maintained within the following limits. Excursions outside of these ranges during or after a storm event trigger Post Event Assessment & Recovery inspection protocols.

- Relative Humidity: 25 – 55%
- Temperature: 60 – 90°F
- Rate of Change: No more than 10% RH or 10°F per 24 Hour Period
- Moisture Content of Wood Products at Installation: 6 – 12% (Kiln-Dried Interior Work)

MATERIAL SPECIFIC PROTECTION MEASURES

Allegheny Millwork's protection strategies depend on the products state: stored, staged for install or installed, and its vulnerability profile from the Moisture Intolerance by Product.

ARCHITECTURAL WOODWORK IN INTERIOR STORAGE

Architectural woodwork manufactured to AWI/AWS Premium or Custom Grade represents significant schedule and dollar value and is effectively unrepairable if water damaged. Apply the strictest protection.

- All prefabricated millwork, casework, doors and architectural panels shall be staged in the interior core of the building, away from exterior walls and glazing.
- If interior staging is not possible at a Level 2 Alert, return undelivered items to the supplier's warehouse and hold onsite items in the most protected available location.
- Elevate all items a minimum of six (6) inches above slab on pallets or dunnage to avoid ground-water migration and potential flood intrusion.
- Maintain factory packaging until installation. Factory wrap is specifically designed for protection and should not be prematurely discarded.
- Cover staged items with a breathable woven cover (Thermo-Lite or equivalent); avoid direct poly contact which traps condensation and can ghost veneer finishes.
- Over the breathable cover, stage a secondary 6-mil poly sheet that can be quickly deployed at Level 3 to shed water in the event of envelope breach.
- Photograph each item with its Scope Item Number/Shop Drawing Reference before covering. Retain for insurance documentation.

ARCHITECTURAL WOOD & PLASTIC LAMINATE CASEWORK

- Installed Casework with Exposed Interiors: close all doors and drawers at Level 2. Drape cabinet runs with moving blankets then a 6-mil poly sheet at Level 3
- Weight the poly at floor level with sandbags (25 lbs.) or unopened material cartons. Never attached protective coverings to finished surfaces with adhesive tape.
- Staged Casework Awaiting Installation: keep fully crated. Do not uncrate until the building is substantially dried-in and conditioned.
- Countertops (Solid Surface, Stone Composite, Wood): store flat, fully supported, protected from impact. A warped or cracked top cannot be straightened or repaired.
- Toe Kicks and Exposed End Panels: place absorbent pads at floor level below cabinets to capture any water migration.
- Coordinate with Plumbing and Electrical trades to cap or close any rough-ins serving cabinetry before Level 3.

WOOD PANELING (FLUSH, STILE-AND-RAIL, ORNAMENTAL)

Installed paneling presents the single highest field risk in Allegheny Millwork's scope. Once mounted, it cannot be relocated and protective coverage is the only option.

- Prefabricate Paneling Coverage Kits at Project Mobilization: full height 6-mil poly sheets, prelabeled by room and wall, staged within the room they protect.
- At Level 3, hang poly from temporary wood furring or adhesive hooks installed at the ceiling grid line. Allow poly to drape across the face of the paneling.
- Weight bottom of poly drape with sandbags at floor, contiguous with the wall base.
- Never use painter's tape, masking tape or any adhesive directly on panel surfaces. Tape residue damaged factory finishes.
- For Matched Grain Veneer Paneling: photograph each wall pre-event at high resolution with labeled key elevations. A single damaged panel may require resequencing from the original flitch, which may no longer be available from the supplier.
- Raised-Panel and Ornamental Work: pad corners and profile details with foam or cardboard corner guards before poly drape.

WOOD STAIRS, RAILINGS & STANDING/RUNNING TRIM

- Installed Stair Parts (Treads, Risers, Stringers, Rails, Balusters): cover with ram board at the tread level, then drape the rail assembly with moving blankets and poly.
- Protect handrail terminations with fitted caps or padded sleeves. Newels should be blanket wrapped.
- Running Trim (Base, Casing, Crown) at Vulnerable Locations Such as Under Windows and Exterior Door Openings: drape with poly from top of trim to floor line and extend poly twelve (12) inches onto the floor.
- Standing Trim (Paneled Jambs, Pilasters, Column Wraps): wrap with padded blankets and secure with elastic banding. Never tape.
- Staged Trim Packages: keep in original banding, stacked on edge in the building core on dunnage.
- Stair landings and balcony balustrades adjacent to openings receive priority coverage at Level 3.

ARCHITECTURAL WOOD DOORS & FRAMES

- Pre-Hung Doors: Keep in factory packaging until ready to set. Factory packaging is optimized for moisture protection.
- Installed Doors: close and latch at Level 3. Tape painter's plastic or a cardboard face protector to the frame only, never to the door face.
- Veneer Doors are particularly sensitive to humidity swings and will warp if one face is exposed to elevated humidity while the other remains conditioned. Maintain equal environmental conditions on both faces.
- Wood Frames (Pre-Finished or Field-Finished): protect jambs with corner guards. If doors are not yet hung, install temporary plywood closure panels in the opening at Level 3.
- Coordination with Division 08, Openings for hardware removal or protection as appropriate.

INTERIOR PLASTIC FABRICATIONS & COMPOSITES

- Solid Surface (Acrylic & Polyester Based) Fabrications: low moisture sensitivity but vulnerable to impact fracture. Store flat and protect from falling debris.
- Plastic Laminate Sheets (Pre-Installed): store flat, fully supported, and dry. Edge delamination occurs rapidly with moisture.
- FRP Wall Panels: installed panels are moisture tolerant but adhesive bonding can fail under prolonged humidity. Inspect edge lifting after any envelope breach.
- PVC & Composite Trim: UV-Stable and water tolerant but thermally expansive. Secure bundles with double banding as strapping tends to loosen in heat.
- Simulated Stone Fabrications (Interior): protect from impact. Moisture tolerance varies by manufacturer. Confirm with submittals.
- Adhesives and Sealants: store per manufacturer temperature range. Do not allow exposure above 90°F or below freezing.

ENVIRONMENTAL CONTROL DURING & AFTER EVENT

- Before the season begins, position battery backup hygrothermograph data loggers in each room containing installed millwork. Record thirty (30) days of baseline readings.
- Pre-stage roll goods of 6-mil poly, furring strips, cap nails and a hammer at each stairwell for rapid emergency envelope dry-in.
- Confirm availability of portable dehumidifiers and air movers through the General Contractor or a pre-selected IICRC Certified restoration vendor. A standing purchase order is preferred over post-event procurement given regional demand surge.
- During the Event: where the building has generator backed HVAC, maintain conditioning. Where not, expect uncontrolled humidity swings.
- After Any Envelope Breach: deploy dry-in within 4 hours. Restore conditioning within 24 hours. Record humidity and temperature at 4 hour intervals until stable.
- If humidity exceeds 60% for more than 48 hours in a room containing installed veneer millwork, coordinate immediately with the architect and supplier regarding potential rejection and necessary replacements.

BUILDING ENVELOPE COORDINATION

Allegheny Millwork's protection depends entirely on the continued integrity of the building envelope. Close coordination with other trades is essential.

- **Division 07 (Thermal & Moisture Protection)**
 - Confirm roofing is tied down and flashed
 - Verify no unfinished penetrations remain
 - Coordinate temporary membrane repairs
- **Division 08 (Openings)**
 - Confirm all glazing is either installed to hurricane rated standard or covered with pre-cut plywood opening protection
 - Confirm exterior door closures are operational and latched
- **Division 09 (Finishes)**
 - Coordinate protection of adjacent finishes
 - Flooring
 - Wall Finishes
 - Ceilings
 - Often share protection measures with millwork
- **Division 22 (Plumbing) & Division 26 (Electrical)**
 - Confirm rough-ins, risers and service entrances are weathertight
 - Drain or cap any exposed piping that could freeze or leak
- **Division 23 (HVAC)**
 - Coordinate conditioning strategy during and after the event
 - Confirm generator backup for critical dehumidification

BUILDING STATUS CLASSIFICATIONS

Allegheny Millwork's protection approach varies significantly by the project's envelope status at the time of the event.

Envelope Status	Interior Trades Exposed	Primary Protection Strategy
Not Dried-In	No Interior Trades Work Shall be Installed. Staged Material Only.	Return Material to Supplier. Do Not Mobilize Crew
Dried-In, Not Conditioned	High: Humidity Swings Will Occur	Minimize Onsite Material. Protect Staged Material. Data Logger Monitoring
Dried-In, Conditioned, Generator Backed	Moderate: Envelope Breach Still Possible	Full Material Specific Protection Protocol. Maintain Conditioning
Substantially Complete, Occupied Conditioning	Low: Closest to Occupied Condition	Full Material Specific Protection Protocol. Coordinate with Owner's Facilities

PERSONNEL SAFETY & DEMOBILIZATION

- Allegheny Millwork, its subcontractors, suppliers and installers shall cease work when sustained winds at the site reach 30 mph or gusts reach 40 mph, whichever occurs first.
- No Allegheny Millwork employee, subcontractor, supplier or installer shall remain on site after a mandatory evacuation order for the zone has been issued.
- Conduct a full headcount during demobilization. Record time of departure and destination of each employee.
- Provide each employee with a printed copy of the Emergency Contact Roster (Appendix A) and the Post-Event Reentry Procedure.
- Workers with special needs, pregnancy or recent medical events shall be released at Level 2.
- Language appropriate plan summaries shall be posted for any crew with limited English proficiency workers.

DOCUMENTATION & INSURANCE REQUIREMENTS

Allegheny Millwork's products carry unusually high dollar-per-square-foot value and long replacement lead times. Insurance recovery depends on documentation of pre-event conditions.

- High-resolution photographs of every installed millwork run, keyed to room number and shop-drawing reference
- Video walkthrough of each completed space, narrated with location and scope references
- Moisture meter readings (pin-type and capacitance) for all installed veneer work, recorded monthly during storage and weekly once installed
- Environmental data-logger records (temperature and humidity) for each room with installed architectural woodwork
- Copies of shop drawings, AWI QCP certificates, supplier shipping tickets, and material COIs retained in the project record
- Builder's risk policy number, carrier, and adjuster contact posted in the site office and the Division 06 trailer
- Signed and dated copies of the Section 10 checklists retained in the project record
- Mobilization photograph set repeated at substantial completion of each millwork phase

POST-EVENT ASSESSMENT & RECOVERY

No personnel shall reenter the jobsite until local authorities authorize return and the General Contractor's Safety Officer confirms basic site safety (no downed wires, no gas leaks, structural stability confirmed).

INITIAL DAMAGE ASSESSMENT (FIRST 24 HOURS)

1. Confirm all personnel is accounted for. Report any missing workers to the General Contractor and local authorities
2. Walk the site with the Safety Officer. Identify structural and biological hazards before entering interior areas.
3. Identify envelope breaches first. The water intrusion clock starts at breach, not at entry.
4. Photograph all damage in place before moving anything. These photos are critical for insurance
5. Retrieve environmental data loggers. Preserve records for claims.
6. Deploy emergency envelope dry-in at any breach in a room containing installed millwork.
7. Identify water-exposed architectural woodwork. Segregate from the dry stock.
8. Notify builder's risk insurer within the policy reporting window (typically 48 – 72 hours).
9. Notify architectural woodwork supplier. Long-lead items may need reordering before insurance adjudication completes.

MATERIAL DISPOSITION

- Veneer paneling and casework with any water intrusion: presumptively rejected; the AWI QCP does not recognize field-dried water-damaged veneered products
- Solid-wood trim and standing trim with water exposure: moisture-test; may be salvageable if dried within acceptable timeframe and below 12% MC
- Plastic laminate casework: inspect for edge delamination; reject if any delamination is present
- Architectural wood doors: check for warp, telegraphing of core defects, and finish damage; any veneer separation or measurable warp triggers rejection
- MDF-core millwork: presumptively rejected with any moisture contact — MDF does not recover
- Solid surface and FRP: inspect for impact damage and adhesive failure; most items salvageable absent visible defect
- Debris-impacted items: even minor impact can cause hairline cracks in veneer that will propagate over time; document and consult architect and supplier
- Do not dispose of any damaged material before the insurer's adjuster has documented or waived inspection

DRYING & ENVIRONMENTAL RESTORATION

- Follow IICRC S500 (Water Damage Restoration) for all wetted areas containing interior trades work
- Target: restore interior conditions to 25–55% RH and 60–90°F within 72 hours
- Deploy commercial dehumidifiers and air movers; target grains per pound (GPP) below 75 for restoration drying
- Document humidity and temperature at 4-hour intervals at multiple locations in each affected room until stable for at least 72 hours

- Do not install replacement millwork until environmental conditions have been stable and documented for a minimum of 14 days
- Coordinate with Division 07 for any insulation that was wetted; wet insulation in a wall assembly will cause mold regardless of finished-trades condition

CHECKLISTS

The following checklists shall be completed, signed and retained in the project folder. One master set is kept by the Allegheny Millwork Project Manager and a copy is provided to the General Contractor within 24 hours of completion.

1. Checklist A: Pre-Season Checklist (Level 1)
2. Checklist B: 72 – 96 Hour Checklist (Level 2: Watch Issued)
3. Checklist C: 36 – 48 Hour Checklist (Level 3: Warning Issued)
4. Checklist D: Post-Event Checklist (Level 4: All Clear)