



TOOLBOX TALK — WEEKLY SAFETY MEETING

Millwork | Carpentry | Interior Finishes | Material Handling

WEEK 36

Date: Supervisor:

Project / Job Name:

TOPIC: Fire Prevention in Millwork & Finish Carpentry

OVERVIEW:

Millwork shops and finish carpentry work areas are high-risk environments for fire. Fine wood dust is combustible and can accumulate rapidly. Solvent-based finishes are flammable liquids. Electrical equipment in dusty environments creates ignition hazards. Fire prevention in our trade requires active

TALKING POINTS — Read to Crew:

1. Wood dust is not just a respiratory hazard — it is a fuel. Fine dust that settles on horizontal surfaces, equipment motors, and electrical panels can ignite from a spark, a hot motor, or even a static discharge. The concentration of wood dust needed to create an explosive mixture is surprisingly low. Keep all surfaces clean, all equipment dusted, and all dust collection systems
2. Flammable finishes, solvents, and adhesives must be stored in approved flammable storage cabinets when not in active use. These cabinets are designed to contain a fire for a minimum of 10 minutes, providing time for evacuation and response. Do not store flammable materials in cardboard boxes, on open shelves, or near ignition sources. Keep quantities of flammable materials in the work area to
3. Know where your fire extinguishers are before you need them. OSHA requires a fire extinguisher within 75 feet of any point in a work area where flammable liquids are used. Verify that extinguishers are charged, inspected within the last year, and accessible — not blocked by materials or equipment. An extinguisher is useless if you cannot reach it in an emergency.
4. Call 911 immediately if a fire is not immediately controlled by one extinguisher discharge. Do not continue fighting a growing fire. Evacuate the building, account for all crew members, and do not re-enter until emergency services have cleared the scene. No material or tool is worth your life. The evacuation route and assembly point for this project are posted at the entry — make sure you

DISCUSSION QUESTIONS — Ask Your Crew:

- Q1: Where are the fire extinguishers on this site, and when were they last inspected?
Q2: What is the evacuation plan and crew assembly point for this project?

KEY SAFETY POINTS:

- Sweep and vacuum sawdust at the end of every shift without exception
- Store all flammable finishes in an approved flammable storage cabinet
- Keep a charged fire extinguisher within 75 ft of all flammable liquid use
- No open flames within 50 ft of any solvent-based product application
- Know the location of all fire extinguishers and pull stations on your site

Crew sign-in sheet on page 2 — all 30 crew members sign on the following page.



CREW SIGN-IN SHEET

WEEK 36

By signing, I confirm I attended this toolbox talk and understand the topic discussed.

#	PRINT NAME	SIGNATURE (click to sign in Acrobat)	#	PRINT NAME	SIGNATURE (click to sign in Acrobat)
01		click to sign	16		click to sign
02		click to sign	17		click to sign
03		click to sign	18		click to sign
04		click to sign	19		click to sign
05		click to sign	20		click to sign
06		click to sign	21		click to sign
07		click to sign	22		click to sign
08		click to sign	23		click to sign
09		click to sign	24		click to sign
10		click to sign	25		click to sign
11		click to sign	26		click to sign
12		click to sign	27		click to sign
13		click to sign	28		click to sign
14		click to sign	29		click to sign
15		click to sign	30		click to sign