



TOOLBOX TALK — WEEKLY SAFETY MEETING

Millwork | Carpentry | Interior Finishes | Material Handling

WEEK 40

Date: Supervisor:

Project / Job Name:

TOPIC: Door Installation Safety

OVERVIEW:

Prehung door installation is a physically demanding task involving heavy, awkward units, fastening in tight doorway openings, and constant use of the hands near moving door components. Finger and hand injuries from pinch points between the door and the jamb are among the most common injuries in interior

TALKING POINTS — Read to Crew:

1. Prehung door units can weigh 80 to 150 pounds or more depending on size and construction. Solid-core doors, fire-rated doors, and exterior doors are significantly heavier than hollow-core interior doors. Never attempt to carry a prehung unit solo — always use two people, carry from the frame not the door slab, and agree on a set-down location and procedure before you lift. A dropped
2. Pinch points between the door and the jamb cause some of the most painful and serious finger injuries in finish carpentry. These injuries happen when the door swings unexpectedly, when the installer is testing the swing while fingers are still in the gap, or when a door held open by a wedge releases. Develop the habit of moving your fingers completely clear of the jamb gap before
3. Use appropriate tools and jigs to hold doors plumb and level during installation rather than relying on body position to control the door while fastening. Door installation jacks, adjustable door horses, and temporary wedges allow both hands to be used for fastening rather than one hand holding the door and one hand driving fasteners. A door that shifts during fastening is difficult
4. Protect finished jambs and door faces throughout the installation process. Scuffs, dents, and gauge marks from hammers, drills, and pry bars during installation require touch-up or replacement that adds cost and time. Use tape on jamb faces before drilling and shiming. Use a drill stop to prevent bit overtravel. Every finish damage avoided is a quality win and a time savings for the

DISCUSSION QUESTIONS — Ask Your Crew:

- Q1: Walk through the two-person carry procedure for a prehung door unit — who leads, how do you communicate?
Q2: Has anyone been injured or had a close call with a door pinch point? What happened?

KEY SAFETY POINTS:

- Always two-person carry for all prehung door units — never solo
- Watch all finger placement when swinging or testing a door in the opening
- Use wedges or door horses to hold units upright during installation
- Protect finished jambs with tape — edge damage leads to rework and cost
- Secure the door open during installation to prevent unexpected swinging

Crew sign-in sheet on page 2 — all 30 crew members sign on the following page.



CREW SIGN-IN SHEET

WEEK 40

By signing, I confirm I attended this toolbox talk and understand the topic discussed.

#	PRINT NAME	SIGNATURE (click to sign in Acrobat)	#	PRINT NAME	SIGNATURE (click to sign in Acrobat)
01		click to sign	16		click to sign
02		click to sign	17		click to sign
03		click to sign	18		click to sign
04		click to sign	19		click to sign
05		click to sign	20		click to sign
06		click to sign	21		click to sign
07		click to sign	22		click to sign
08		click to sign	23		click to sign
09		click to sign	24		click to sign
10		click to sign	25		click to sign
11		click to sign	26		click to sign
12		click to sign	27		click to sign
13		click to sign	28		click to sign
14		click to sign	29		click to sign
15		click to sign	30		click to sign